



# RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

## Weber #8

			Start 7-30-19
			Finish 8-5-19
7	soil	7	
28	clay/gravel	35	
209	shale	244	
39	lime	283	
18	shale	301	
42	lime	343	
72	shale	415	
101	lime	516	Set 40' 7" w/5sxs
29	shale	545	Ran 1089.1' of 2 7/8
130	lime	675	cemented to the surface
165	shale	840	135sxs
30	lime	870	
60	shale	930	
31	lime	961	
15	shale	976	
10	lime	986	
11	shale	997	
6	lime	1003	
7	shale	1010	
5	lime	1015	
9	shale	1024	
5	sandy shale	1029	show
10	oil sand	1039	good show
19	shale	1058	
6	oil sand	1064	good show
47	shale	1111	T.D