



RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

Webber #6

			Start 8-5-19
			Finish 8-15-19
8	soil	8	
25	clay/gravel	33	
208	shale	241	
38	lime	279	
24	shale	303	
41	lime	344	
64	shale	408	
107	lime	515	Set 40' 7" w/5sxs
28	shale	543	Ran 1087.1' of 2 7/8
131	lime	674	cemented to the surface
165	shale	839	135sxs
34	lime	873	
54	shale	927	
31	lime	958	
15	shale	973	
10	lime	983	
12	shale	995	
6	lime	1001	
6	shale	1007	
5	lime	1012	
13	shale	1025	
3	sandy shale	1028	
11	oil sand	1039	
4	dk sand	1043	
12	shale	1055	
3	oil sand	1058	good show
2	dk sand	1060	show
50	shale	1110	T.D