

Ackarman Hardware & Lumber
 Ackarman Inc
 160 East Main St
 Sedan, KS 67361
 620-725-3103

CUSTOMER COPY



INVOICE

1707-100409 PAGE 1 OF 1

| SOLD TO |
|---|
| STAN MILLER SM OIL & GAS P. O. BOX 189 SKIATOOK OK 74070 |

| JOB ADDRESS |
|---|
| STAN MILLER SM OIL & GAS P. O. BOX 189 SKIATOOK OK 74070 918-396-3020 |

| ACCOUNT | JOB |
|--------------|----------------------|
| 00680 | 0 |
| SOLD ON | 7/27/2017 1:10:19 PM |
| CUST PICKUP | |
| BRANCH | 1000 |
| CUSTOMER PO# | STAN |
| STATION | A2 |
| CASHIER | DK |
| SALESPERSON | CM |
| ORDER ENTRY | |

| Quantity | UM | Item | Description | D | T | Price | Per | Amount |
|----------|------|---------|------------------------------------|---|---|---------|------|--------|
| 10 | EACH | MP10092 | PORTLAND CEMENT 92.6# | N | Y | 13.9500 | EACH | 139.50 |
| 4 | PKG | HKKC105 | KC105 1" KEY RING 2/CD | | Y | 1.9900 | PKG | 7.96 |
| | | | <i>TRUST #4 SURFACE CEMENT</i> | | | | | |
| | | | <i>API # 15-019 - 27576</i> | | | | | |

Payment Method(s) Buyer: STAN MILLER

Charge to Acct 162.21

| | | |
|-------------------------------|-----------|---------------|
| KS 10.00% | SubTotal | 147.46 |
| | Sales Tax | 14.75 |
| | Deposit | |
| Please Pay This Amount | | 162.21 |

[Signature]
 Signature STAN MILLER *AK*

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3469**
 Foreman Kevin McCoy
 Camp EUREKA

| Date | Cust. ID # | Lease & Well Number | Section | Township | Range | County | State | |
|---------------------------------|------------|---------------------|----------------------------------|----------|----------|----------|--------|--------|
| 8-25-17 | 1180 | Miller Trust #4 | | | | CQ | Ks | |
| Customer S. M. OIL & GAS | | | Safety Meeting KM DG GM | | Unit # | Driver | Unit # | Driver |
| Mailing Address P.O. Box 189 | | | | | 105 | DAVE G. | | |
| City SKIATOOK | | | State OK | | 113 | KEVIN M. | | |
| Zip Code 74070 | | | | | 114 | | | |
| | | | | | 127 R.U. | GARY M. | | |

Job Type Longstring Hole Depth 1630' Slurry Vol. 34 BBL LEAD Tubing _____
20 BBL TAIL
 Casing Depth 1606' Hole Size 6 3/4" Slurry Wt. 12.8* - 14* Drill Pipe _____
 Casing Size & Wt. 4 1/2 11.60* Cement Left in Casing 0' Water Gal/SK _____ Other _____
 Displacement 25 BBL Displacement PSI 700 Bump Plug to 1100 PSI BPM _____

Remarks: SAFETY Meeting: Rig up to 4 1/2 casing. BREAK Circulation w/ 35 BBL Fresh water. Pump 500* Gel Flush w/ Hulls, 5 BBL water spacer. MIXED 125 SKS 50/50 Pozmix Cement w/ 6% Gel, 1* PhenoSeal /SK @ 12.8*/gal = 34 BBL Slurry. TAIL in w/ 75 SKS o/wc Cement w/ 1* PhenoSeal /SK @ 14*/gal = 20 BBL Slurry. WASH out Pump & Lines. Shut down. Release Plug. Displace Plug to SEAT w/ 25.5 BBL Fresh water. FINAL Pumping Pressure 700 PSI. Bump Plug to 1100 PSI. WAIT 2 MINS. Release Pressure. Float Heid. Shut in @ 0 PSI. Good Cement Returns to SURFACE = 10 BBL Slurry to Pit. Job Complete. Rig down.

| Code | Qty or Units | Description of Product or Services | Unit Price | Total |
|---|--------------|------------------------------------|------------|---------|
| C 102 | 1 | Pump Charge | 1050.00 | 1050.00 |
| C 107 | 30 | Mileage | 3.95 | 118.50 |
| C 204 | 125 SKS | 50/50 Pozmix Cement | 11.25 | 1406.25 |
| C 206 | 630 * | Gel 6% | .20 * | 126.00 |
| C 208 | 125 * | PhenoSeal 1*/SK | 1.25 * | 156.25 |
| C 202 | 75 SKS | OWC Cement | 19.15 | 1436.25 |
| C 208 | 75 * | PhenoSeal 1*/SK | 1.25 * | 93.75 |
| C 206 | 500 * | Gel Flush | .20 * | 100.00 |
| C 214 | 40 * | HULLS | .45 * | 18.00 |
| C 108 A | 9.15 TONS | Ton Mileage | M/c x 2 | 690.00 |
| C 403 | 1 | 4 1/2 Top Rubber Plug | 45.00 | 45.00 |
| C 113 | 3 HRS | BBL VAC TRUCK (C & E OIL) | 85.00 | 255.00 |
| C 224 | 3300 gals | City water | 10.00/1000 | 33.00 |
| <u>THANK YOU</u> | | | | |
| | | | Sub TOTAL | 5528.00 |
| | | | Less 5% | 290.91 |
| | | | Sales Tax | 290.23 |
| | | | 8.5% | |
| Authorization <u>T. McCoy</u> Title _____ | | | Total | 5527.32 |

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.