

Ackarman Hardware & Lumber  
 Ackarman Inc  
 160 East Main St  
 Sedan, KS 67361  
 620-725-3103  
 Fax: 620-725-5688

**CUSTOMER COPY**



**INVOICE**

1710-105812 PAGE 1 OF 1

SOLD TO	JOB ADDRESS
STAN MILLER SM OIL & GAS P. O. BOX 189 SKIATOOK OK 74070	STAN MILLER SM OIL & GAS P. O. BOX 189 SKIATOOK OK 74070 918-396-3020

ACCOUNT	JOB
00680	0
SOLD ON	10/13/2017 8:29:05 AM
CUST PICKUP	
BRANCH	1000
CUSTOMER PO#	
STATION	A2
CASHIER	CAM
SALESPERSON	CM
ORDER ENTRY	

Quantity	UM	Item	Description	D	T	Price	Per	Amount
10	EACH	MP10092	PORTLAND CEMENT 92.6#		Y	14.9500	EACH	149.50
4	EACH	5614714	100A/RS A-21 ROUGH SERV B		Y	3.6900	EACH	14.76
			<i>AG 3"</i>					
			<i>Underwood #112 Surface cement</i>					

Payment Method(s) Buyer: TOM OAST

Charge to Acct 180.69

KS 10.00%	SubTotal	164.26
	Sales Tax	16.43
	Deposit	
<b>Please Pay This Amount</b>		<b>180.69</b>

*[Handwritten Signature]*  
 Signature TOM OAST

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **3559**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
10-19-17	1180	Underwood #112				C9	KS	
Customer	Mailing Address	City	State	Zip Code	Unit #	Driver	Unit #	Driver
S.M. OIL & GAS	P.O. Box 189	SKIATOOK	OK	74070	105	DAVE G.		
					112	JASON H.		
					113	RICK L.		

Job Type Longstring Hole Depth 1630' Slurry Vol. 34 BBL Lead 20 BBL Tail Tubing \_\_\_\_\_  
 Casing Depth 1624' Hole Size 6 3/4 Slurry Wt. 12.8# - 14# Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 25.5 BBL Displacement PSI 850 Bump Plug to 1250 PSI BPM \_\_\_\_\_

Remarks: SAFETY Meeting: Rig up to 4 1/2 casing. BREAK CIRCULATION w/ 50 BBL FRESH WATER. Pump 500# GEL flush w/ HULLS, 5 BBL water spacer. MIXED 125 SKS 50/50 Pozmix Cement w/ 6% GEL, 1# PhenoSeal /SK @ 12.8#/gal = 34 BBL Slurry. Tail in w/ 75 SKS owc Cement w/ 1# PhenoSeal /SK @ 14#/gal = 20 BBL Slurry. wash out Pump & Lines. Shut down. Release Plug. Displace Plug to Seat w/ 25.5 BBL FRESH WATER. FINAL Pumping Pressure 850 PSI. Bump Plug to 1250 PSI. wait 2 mins. Release Pressure. Float Held. Shut in @ 0 PSI. Good Cement Returns to SURFACE = 10 BBL Slurry to Pit. Job Complete. Rig down

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	125 SKS	50/50 Pozmix Cement	11.25	1406.25
C 206	630 #	GEL 6% } Lead Cement	.20 #	126.00
C 208	125 #	PhenoSeal 1#/SK	1.25 #	156.25
C 202	75 SKS	OWC Cement } Tail Cement	19.15	1436.25
C 208	75 #	PhenoSeal 1#/SK	1.25 #	93.75
C 206	500 #	Gel Flush	.20 #	100.00
C 214	40 #	HULLS	.45 #	18.00
C 108 A	9.15 TONS	Ton Mileage BULK TRUCKS x 2	M/C x 2	690.00
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
C 113	3 HRS	80 BBL VAC TRUCK (C & E OIL)	85.00	255.00
C 224	3300 gals	CITY WATER	10.00 / 1000	33.00
			Sub Total	5528.00
			Less 5%	276.40
			Sales Tax	290.23
				8.5%
			Total	5527.31

Authorization witness By Joel Title \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.