

JOB LOG

SWIFT Services, Inc.

DATE	PAGE NO.
5-31-2019	1

CUSTOMER	WELL NO.	LEASE	JOB TYPE	TICKET NO.
Trans Pacific Oil	Fitzler A 1-6	Fitzler A unit	Surface Pipe	032305

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1930							On Location 8 5/8" 23lb/ft
								RTD: 251
	1945							Start 8 5/8" 23lb/ft Casing in Well
	2035							Circulate
	2040	3 1/2	5		✓	100		Pump 5 bbl @ H ₂ O Spacer
	2045	4 1/2	40		✓	150		Mix 165 sks of Standard 2% gel 3% CC CMT @ 14.7ppg
	2055	4 1/2	0		✓	150		start Displace CMT
		4 1/2	10		✓	200		Circulate CMT to Surface * 20 sks *
		4 1/2	15 1/4		✓	250		60 Pump Shut-in
	2100							Release Pressure * Valve Hold *
	2105							Wash-up Trk #112
	2130							Job Complete
								165 sks of Standard CMT 2% gel 3% CC used * 20 sks to Pit *
								Thank You
								Grideon, Preston, Dusty

JOB LOG

SWIFT Services, Inc.

DATE	PAGE NO.
9 Jun 19	1
TICKET NO.	
32215	

CUSTOMER		WELL NO.		LEASE		JOB TYPE		DESCRIPTION OF OPERATION AND MATERIALS	
Trans Pacific				Fritzer unit A					
CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)			
				T	C	TUBING	CASING		
									1756h SA-2 w/ 1/4" floccle
									5 1/2" x 1 1/4" casing 107jts 4448' TD=4451
									Turbolizers - 1,2,3,4, 6,8,10, 166 Bost 1,67
									Part Colloc #67 1688' sleevejt 2126
	0700								on loc TRK 114
	1050								start 5 1/2" x 1 1/4" casing in well
	1248								Drop ball - circulate
	1305	5	12			200			Plug RH - MH Pump 500gal mud flush
		5	20			200			Pump 20 bbl KCL plug
	1312		7						Plug RH - MH 30% - 20%
	1322	4 1/2	36			200			Mix SA-2 cement 1255' @ 15.3 ppg
									Drop latch down plug
									wash out Pump & Line
	1338	6				200			Displace plug
		6	91			300			
		5	107			600			
	1400	5	108			1500			Land plug
									Release pressure to truck - dried up
	1405								wash truck
									Back up
	1435								Job complete
									Thanks
									Braine, Flint & Isaacs