

DATE 10-7-19 TIME 10:00 (AM)

OPERATOR High Plains Production LLC

OPERATOR LICENSE NO. 35161 API# 15- 055-21924-00-00

PLUGGING CONT. Quality Plus / Hurricane LICENSE NO. \_\_\_\_\_

PUSHER None WITH \_\_\_\_\_

LEASE NAME & WELL NO. Mayo 1-9

LEGAL NW SE SW Sec 9-23-32<sup>W</sup> COUNTY Finnery

GPS: Latitude <sup>1254 FSL</sup> 38,06531° N Longitude <sup>3329 FSL</sup> 100,84067° W

TD 2656 PBDT 2648 C.P. \_\_\_\_\_ S.P. 8 5/8 % 391 w/ 275 sx

OTHER CASING 5 1/2 % 2653 W/ 550 (circulated) SX CMT

PERFORATED AT 2581-2589 & 2607-2617

LINER FROM \_\_\_\_\_ TO \_\_\_\_\_ W/ \_\_\_\_\_ SX CMT

MARKER DEPTH Stone Corral - 2005', Permian Top ~ 1150' ±

BOTTOM PLUG \_\_\_\_\_

CASING RECOVERY None

TOP PLUG(S) Fill 5 1/2" csq with cement from 2617' to 0' using 300# hulk and 280 sx amt. Pressure to 350#. Holding. Pump 30sx down the annulus. Pressure to 250#. Holding. Top off 5 1/2" csq with 5 sx.

STARTING TIME 8:00 AM COMPLETION TIME 10:00 AM

TYPE OF CEMENT & CEMENTER 60/40 Por 4% gel Hurricane 5105

PLUGGED THROUGH: CASING - TUBING - DRILL PIPE (CIRCLE ONE)

PLUGGING ORDERS GIVEN BY Ken Sehl PLUGGING WITNESSED BY Ken Sehl

WELL PLUGGED DUE TO COMPLIANCE ISSUE: NO (CIRCLE ONE)