

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **4461**  
 Foreman David Gardner  
 Camp Eureka

API # 15-015-24123

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
5-28-19	1037	Busenitz #2	24	24 S.	4 E.	Butler	KS
Customer			Unit #	Driver		Unit #	Driver
C + G Drilling			105	Jason			
Mailing Address			112	Josh			
701 E. River							
City	State	Zip Code					
Eureka	KS	67045					

Job Type Surface Hole Depth 241' K.B. Slurry Vol. 25 Bbl Tubing \_\_\_\_\_  
 Casing Depth 225.18' G.L. Hole Size 12 1/4" Slurry Wt. 15# Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 9 5/8" Cement Left in Casing 15' +/- Water Gal/SK 6.5 Other \_\_\_\_\_  
 Displacement 116 3/4 Bbl Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting. Rig upto 9 5/8" casing w/ 8 5/8" Landing Joint + change over. Break circulation w/ 10 Bbl fresh water. Mixed 105 sbs Class 'A' Cement w/ 3% Cactz + 2% Gel @ 15#/gal., yield 1.35 = 25 Bbl Slurry. Displace w/ 116 3/4 Bbl fresh water. Good cement returns to surface = 5 Bbl slurry to Pit. Shut casing in. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C101	1	Pump Charge		
C107	10	Mileage From Eldorado #217	890.00	890.00
			4.20	42.00
C200	105 sbs	Class 'A' Cement	15.75	1653.75
C205	300#	Cactz @ 3%	.63	189.00
C206	200#	Gel @ 2%	.21	42.00
C108A	4.935 Tons	Ton Mileage - Bulk Truck	m/c	365.00
<u>Thank You</u>				
			Sub Total	3,181.75
			Less 5%	165.21
			Sales Tax	122.51
Authorization <u>by Sudd Gulick</u> Title <u>Tool Pusher</u>			Total	3,139.05

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.



810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. **4518**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-1-19	1037	Busenitz #2	24	24S	4E	Butler	Ks
Customer	Mailing Address		Unit #	Driver	Unit #	Driver	
C & G DRILLING	701 E. RIVER		104	Alan M.			
City	State	Zip Code	110	Calb G.			
EUREKA	Ks	67045					

Job Type Longstring Hole Depth 2730' KB Slurry Vol. 37 BBL ON L/S Tubing \_\_\_\_\_  
 Casing Depth 2712.80' G.L. Hole Size 7 7/8 Slurry Wt. 13.8" Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 65.5 Displacement PSI 800 Bump Plug to 1400 PSI BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 5 1/2 casing w/ rotating swivel. Break circulation w/ 15 BBL fresh water. Mixed 115 SKS THICK Set Cement w/ 5" KOL-SEAL /SK 2" Pheno Seal /SK @ 13.8" /gal, yield 1.80 = 37 BBL slurry. (Plug Rat Hole 20 SKS, M.H 15 SKS) wash out pump & lines, shut down. Release Latch down Plug. Displace Plug to seat w/ 65.5 BBL Fresh water. (First 20 BBL w/ KCL) FINAL pumping pressure 800 PSI Bump Plug to 1400 PSI. Release pressure, float & Plug held. Good circulation @ ALL times while cementing. Job Complete. Rig down.

Plug R.H. w/ 20 SKS Plug M.H. w/ 15 SKS  
CENTRALIZERS ON #1, 2, 4, 5, 6.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1100.00	1100.00
C 107	10	Mileage From El Dorado RM	4.20	42.00
C 201	150	THICK Set Cement (115 SKS Production casing)	20.50	3075.00
C 207	750 *	KOL-SEAL 5" /SK	.47 *	352.50
C 208	300 *	PHENO-SEAL 2" /SK	1.30 *	390.00
C 108A	7.05 TONS	TON Mileage	M/C	365.00
C 222	2 GAL	KCL (in first 20 BBL of Displacement water)	30.00	60.00
C 421	1	5 1/2 LATCH down Plug	242.00	242.00
C 661	1	5 1/2 AFU-FLOAT shoe	309.00	309.00
C 504	5	5 1/2 x 7 7/8 CENTRALIZERS	50.00	250.00
THANK YOU			Sub Total	6185.50
			Less 5%	324.48
			Sales Tax	304.10
			Total	6165.12

Authorization By Tim Gulick

Title \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.