

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. 4551  
 Foreman Russell McCoy  
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-6-19	1037	Busenitz 14-1	14	24S	4E	Butler	KS
Customer C+G Drilling			Unit #	Driver	Unit #	Driver	
Mailing Address 701 E. River			104	Alan - M			
City Eureka			112	Caleb			
State KS			141	Zevi			
Zip Code							

Job Type Longstring Hole Depth 2730 KB Slurry Vol. 38 45 Tubing \_\_\_\_\_  
 Casing Depth 2711 G.L. Hole Size 7 7/8 Slurry Wt. 13.8 Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 used Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 66 Bbl Displacement PSI 750 Bump Plug to 1400 BPM 5

Remarks: Safety Meeting + Job Procedure Rig to 5 1/2 casing w/ Rotating Swivel  
BREAK Circulation w/ 15 Bbl Fresh water mix 115 SKs T.S. cement w/ 5# Kolseal  
2# Phenoseal @ 13.8 w/ yield of 1.8 = 38 Bbl Slurry (Plug Rathwick + M.H.)  
Wash out Pump + Lines Release 5 1/2 Latch Down Plug Displacement 66 Bbl  
Water Final Pump PSI 750# Seat Plug to 1400# Release PSI Plug Held.  
NOTE GOOD circulation @ All times During cementing Procedure.  
Job Complete, Tear Down. THANK YOU Russell McCoy

Centralizers # 1 # 3 # 4 # 5 # 7 # 17 Zones 2460-2540 Mississippi  
 NOTE Plug R.H. w/ 20 SKs M.H. w/ 15 SKs 2090 - K.C.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge		
C-107	10	Mileage From Eldorado	1100.00	1100.00
			4.20	42.00
C-201	150	SKs Thick Set cement (115 For Productive)	20.50	3075.00
C-208	300#	Phenoseal = 2# Per/SK	1.30	390.00
C-207	750#	Kolseal = 5# Per/SK	.47	352.50
C-108a	7.05	Ten Mileage		
C-222	2	gallon KLL mixed in First 20 Bbl Displacement	30.00	60.00
C-421	1	5 1/2 Latch Down Plug	242.00	242.00
C-661	1	5 1/2 AFU Float Shoe	309.00	309.00
C-504	5	5 1/2 x 7 7/8 Centralizers	50.00	250.00
			SUBTOTAL	6185.50
			- 5%	324.78
			Sales Tax	304.10
Authorization <u>Witnessed by Tim</u> Title <u>owner</u>			Total	6165.12

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.



810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **4707**  
 Foreman Russell McCoy  
 Camp Eureka AB

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
	1037	Rusenitz 14-1	14	24	4 E	Butler	Ks
Customer <u>C+G Drg</u>			Unit #	Driver	Unit #	Driver	
Mailing Address <u>701 E. River</u>			106	Zev			
City <u>Eureka</u>			141	Josh			
State <u>Ks</u>			128	Josh			
Zip Code <u>67045</u>							

Job Type Acid Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 238  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 used Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 90 Bbl Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety meeting + Job Procedure. Packer set 90' Above Perf's 2460-94  
Stage 2 mult Acid + Swab Back on 8-13-19 Rig to 238 tubing Pump 2 Bbl  
Acid @ 1200# 4 BPM to PreTest Rate + PSI for Ball Off Packer Holding Good  
Annulus Full load Ball Guv w/ 10 Balls Pump Remaining 1416 gallons Acid w/  
2 Ball per Bbl = 34 Bbl Ball Action from 1200-1400 w/ Break Back's During Ball  
Job Final Rate 4.6 BPM 1400# w/ 10 Bbl over Flush shut Down, Release Ball's  
wait 5 min Resume Pumping @ 4.6 BPM 1100# After Ball Release. Flush  
w/ 90 Bbl salt water @ 1500# 5.8 BPM Isif 500# 15 min 400# Close well  
IN Over night. Job Complete, Tear Down.  
NOTE 136 Bbl TOTAL LOAD THANK YOU  
Russ-AB-Zosh

Code	Qty or Units	Description of Product or Services	Unit Price	Total
A-106	2	Pump Charge <u>Retreat Stage 2</u> Mileage	210.00 N.C.	420.00 -
A-205	1500	gallons 15% H.C.L. Acid	1.75	2625.00
A-213	3	gallons Acid Inhibitor	42.00	126.00
A-210	3	gallons Surface Tension Reducer	33.00	99.00
A-214	6	gallons Non Emulsifier Agent	32.00	192.00
A-215	6	gallons Iron Control	38.00	228.00
A-109	1	Ball Injector Rental	105.00	105.00
A-218	70	1.3 Perf Ball Sealers	2.50	175.00
A-113	2	hr Bu Bbl VAC TACK	90.00	180.00
				4,150.00
			- 5%	(207.95)
			Sales Tax	6.93
			<b>Total</b>	<b>3948.98</b>

Authorization by Tim Gulick Title owner

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.