

KB: 1909 DF DF:

GL:

Vess Oil Corporation

Well: RUSCH A , 2 , 471100--2
 Operator: VESS OIL CORPORATION
 Location: N/2 SE SW 19-12S-15W RUSSELL C
 Legal: SW SEC 19 12S-15W

Dir:

Spud Date:
 Drilling Finished:
 Completion Date:
 First Production:

PUMPING DATA:

PU:
 PM:
 BHP: 2" x 1 1/2" x 12' RWT - 76" MSL
 Anchor:

PRODUCTION FACILITY:

TUBING #1:

Type	#Jts	Size	Wt#/f	Grade	Set@
11.5 Reg;	8	102	2 3/8		2993

ROD:

Type	#Rods	Size	Length
SR	118	3/4	25
PY	1	3/4	6
PY	1	3/4	4

HISTORY:

11/36 COMPLETION
 07/39 DEEPEMED TO 3114
 04/46 REPAIR CSG LEAKS @ 644' W/ 370 SX. DEEPEMED TO 3140.
 09/47 PULLED 5 1/2" LOOSE LINER & DEEPEMED TO REAGAN. RAN & CEMENTED 5 1/2" LINER FROM 2895-3265'. RAN 4 1/2" LOOSE LINER FROM 3255-3310'.
 08/64 CMT'D OFF REAGAN W/ 100 SX. PERF'D LKC A-L ZONES & ACIDIZED W/ 12,250 GAL.
 05/67 WATERFLOOD BEGAN.
 01/73 TA'D WELL
 10/79 PULLED TBG, RODS & PUMP TO USE IN RUSCH A 4. LEFT MA & 1 JT TBG IN.
 01/80 SET BP @ 3056, SET EZ DRILL PKR @ 3000'. SQ LINER TOP W/ 100 SX. PERF @ 2747 & SQ W/ 35 SX HOLE @ 2494-2525. PERF & ACIDIZE PLATT, TORONTO & TOPEKA. TESTED 29 BO, 64 BWPD.
 10/15/97 BHP CHANGE. BBL AND PLUNGER WORE OUT, VLVS LEAKING, FAIRLY CLEAN INSIDE.

20 , #, cond., @14

Sqzd 7"- 644' w/370 sx - 4/46

10 , #, csg, @951
 w/0 sx

Hole 2494-2525' - not sqzd - 1/80

Perf'd & Sqzd - 2747' w/35 sx - 1/80

2700'

2749 -2753 TOPEKA 1/80

TUBING #1:

Type	#Jts	Size	Wt#/f	Grade	Set@
11.5 Reg;	8	102	2 3/8		2993

ROD:

Type	#Rods	Size	Length
SR	118	3/4	25
PY	1	3/4	6
PY	1	3/4	4

HISTORY:

11/36 COMPLETION
 07/39 DEEPEMED TO 3114
 04/46 REPAIR CSG LEAKS @ 644' W/ 370 SX. DEEPEMED TO 3140.
 09/47 PULLED 5 1/2" LOOSE LINER & DEEPEMED TO REAGAN. RAN & CEMENTED 5 1/2" LINER FROM 2895-3265'. RAN 4 1/2" LOOSE LINER FROM 3255-3310'.
 08/64 CMT'D OFF REAGAN W/ 100 SX. PERF'D LKC A-L ZONES & ACIDIZED W/ 12,250 GAL.
 05/67 WATERFLOOD BEGAN.
 01/73 TA'D WELL
 10/79 PULLED TBG, RODS & PUMP TO USE IN RUSCH A 4. LEFT MA & 1 JT TBG IN.
 01/80 SET BP @ 3056, SET EZ DRILL PKR @ 3000'. SQ LINER TOP W/ 100 SX. PERF @ 2747 & SQ W/ 35 SX HOLE @ 2494-2525. PERF & ACIDIZE PLATT, TORONTO & TOPEKA. TESTED 29 BO, 64 BWPD.
 10/15/97 BHP CHANGE. BBL AND PLUNGER WORE OUT, VLVS LEAKING, FAIRLY CLEAN INSIDE.

2926 -2928 PLATT 1/80

2941 -2945 TORONTO 1/80

7 , #, csg, @2937
 w/20 sx

2987 -2992 TORONTO 1/80

3019 -3033 LKC A(2) 8/64

3046 -3048 B 8/64

3068 -3081 D(2) 8/64

3094 -3096 F 8/64

3106 -3120 G(2) 8/64

3155 -3157 H 8/64

3176 -3198 I(2) 8/64

3208 -3210 J 8/64

3228 -3230 K 8/64

3252 -3254 L 8/64
 5 1/2 , #, csg, @3265
 w/275 sx

3265 -3310 Reagan Sd Sqzd 9/47

4 1/2 , #, csg, @3310
 w/Loosesx.

Input by:
 Approved by:
 Last Update:

TOC@ 2895'

CIBP@3000

CIBP@3056

OPBTD: 3255'

TD: 3310'