



HURRICANE SERVICES INC

Remit To: Hurricane Services, Inc.
250 N. Water, Suite 200
Wichita, KS 67202
316-303-9515

Customer:
JAMES PRODUCTION
C/O JIM VERNON
1334 GROUSE RD
YATES CENTER, KS 66783

Invoice Date: 7/31/2019
Invoice #: 0342913
Lease Name: Best
Well #: 1-1
County: Sheridan
Job Number: ICT2199

Date/Description	HRS/QTY	Rate	Total
Cement	0.000	0.000	0.00
Cement Pump 230	1.000	637.500	637.50
Light Eq Mileage	55.000	1.700	93.50
Heavy Eq Mileage	55.000	3.400	187.00
Ton Mileage	590.320	1.275	752.66
H-Plug	240.000	11.050	2,652.00

OK to Pay  

Net Invoice	4,322.66
Sales Tax:	238.94
Total	4,561.60

TERMS: Net 30 days. Interest may be charged on past due invoice at rate of 1 1/2% per month or maximum allowed by applicable state or federal laws. HSI has right to revoke any discounts applied in arriving at net invoice price if invoice is past due. If revoked, full invoice price without discount plus additional sales tax, as applicable, is due immediately and subject to interest charges. Customer agrees to pay all collection costs directly or indirectly incurred by HSI in the event HSI engages a third party to pursue collection of past due invoice.

SALES TAX: Services performed on oil, gas and water wells in Kansas are subject to sales tax, with certain exceptions. HSI relies on the well information provided by the customer in identifying whether the services performed on wells qualify for exemption.

WE APPRECIATE YOUR BUSINESS!



CEMENT TREATMENT REPORT

Customer: James Prod Inc	Well: Best #1-1	Ticket: ICT2199
City, State:	County: Sheridan, KS	Date: 7/31/2019
Field Rep:	S-T-R: Sec1-T7S-R29W	Service: Cement

Downhole Information	
Hole Size:	7 7/8 in
Hole Depth:	4270 ft
Casing Size:	8 5/8 in
Casing Depth:	305 ft
Drill Pipe	4.5 in
Depth:	2580 ft
Tool / Packer:	
Depth:	ft
Displacement:	bbls

Slurry	
Weight:	13.8 # / sx
Water / Sx:	6.89 gal / sx
Yield:	1.42 ft ³ / sx
Bbls / Ft.:	
Depth:	ft
Volume:	bbls
Excess:	%
Total Slurry:	bbls
Total Sacks:	240 sx

Cement Blend		
Product	%	#
Class A	60.0	13536
Gel	4.0	826
CaCl		
Metso		
KolSeal		
Flo-Seal		
Salt		
Fly Ash	40.0	7104
Total		21,466

TIME	RATE	PSI	BBLs	REMARKS	TIME	RATE	PSI	BBLs	REMARKS
5:00				Called for job	11:29				DP @ surface
7:30				Depart Oakley yard	11:30				Rig down & L/D Kelly & Rathole
9:00				Arrive on locn. Rig RIH w/ DP to 2580'	12:00	3.3	70	7.50	Plug rathole w/ 30sx mixed @ 13.8ppg
9:05				JSA, discuss moving, spotting & rig-up					Y - 1.42cuft/sk, MW - 6.89g/sk
9:10				Move on, spot & rig-up	12:03				Down
9:15				DP @ 2580'	12:05	3.3	70	2.50	Plug 40' - 0' w/ 10sx mixed @ 13.8ppg
9:25				Rig-up complete					Shutdown. 1.5bbls / 6sx
				Plug #1 2580' - 2370'					Y - 1.42cuft/sk, MW - 6.89g/sk
9:29	3.5	200.0	5.0	Pump H2O ahead	12:07				Down
9:31	4.1	230.0	12.5	Mix & pump 50sx slurry @ 13.8ppg	12:08				Wash-up pumps & lines
				Y - 1.42cuft/sk, MW - 6.89g/sk	12:15				Rig down & rack-up equipment
9:34	3.4	110.0	2.0	Pump H2O behind	12:45				Rig down complete
9:40	8.0	250.0	31.6	Rig displace w/ mud	13:00				JSA, discuss journey management
9:45				Rig POH to 1600'	13:00				Depart locn
10:15				DP @ 1650'. Fill hole					
				Plug #2 1650' - 1230'					
10:20	3.5	120.0	5.0	Pump H2O ahead					
10:22	5.0	480.0	25.3	Mix & pump 100sx slurry @ 13.8ppg					
				Y - 1.42cuft/sk, MW - 6.89g/sk					
10:28	3.3	130.0	2.0	Pump H2O behind					
10:32	8.0	150.0	15.0	Displace w/ H2O					Thanks for calling Hurricane Svcs Inc.
10:35				Rig POH to 920'					
11:08				DP @ 350'. Fill hole.					
				Plug #3 350' - 152'					
11:11	3.3	200.0	25.3	Mix & pump 50sx slurry @ 13.8ppg					
				Y - 1.42cuft/sk, MW - 6.89g/sk					
11:14	3.3	120.0	2.6	Displace w/ H2O					
11:16				Rig POH to surface'					

CREW	UNIT
Cementer: Scott Green	74
Pump Operator: Josh Mosler	230
Bulk #1: Jesse Jones	242
Bulk #2:	

SUMMARY		
Average Rate	Average Pressure	Total Fluid
4.15556 bpm	177.50 psi	136.30 bbls



HURRICANE SERVICES INC

Remit To: Hurricane Services, Inc.
250 N. Water, Suite 200
Wichita, KS 67202
316-303-9515

Customer:

JAMES PRODUCTION
C/O JIM VERNON
1334 GROUSE RD
YATES CENTER, KS 66783

Invoice Date: 7/24/2019
Invoice #: 0342764
Lease Name: Best
Well #: 1-1 (New)
County: Sheridan
Job Number: ICT2176

Date/Description	HRS/QTY	Rate	Total
Surface	0.000	0.000	0.00
Heavy Eq Mileage	40.000	3.400	136.00
Light Eq Mileage	40.000	1.700	68.00
Ton Mileage	396.000	1.275	504.90
Cement pump #231	1.000	637.500	637.50
H-325	200.000	17.000	3,400.00

OK To Pay JAV

Total 4,746.40

TERMS: Net 30 days. Interest may be charged on past due invoice at rate of 1 ½% per month or maximum allowed by applicable state or federal laws. HSI has right to revoke any discounts applied in arriving at net invoice price if invoice is past due. If revoked, full invoice price without discount plus additional sales tax, as applicable, is due immediately and subject to interest charges. Customer agrees to pay all collection costs directly or indirectly incurred by HSI in the event HSI engages a third party to pursue collection of past due invoice.

SALES TAX: Services performed on oil, gas and water wells in Kansas are subject to sales tax, with certain exceptions. HSI relies on the well information provided by the customer in identifying whether the services performed on wells qualify for exemption.

WE APPRECIATE YOUR BUSINESS!

