



PRESSURE PUMPING LLC  
PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

100848  
41046

INV901191

TICKET NUMBER 55624 ✓  
LOCATION Chanute, KS  
FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT  
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/20/19	4015	Wingert # I-1	NW 9	17	22	ML
CUSTOMER JTC Oil Inc						
MAILING ADDRESS 35790 Plum Creek Rd						
CITY Osawatomie		STATE KS	ZIP CODE 66064			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			709	Casey Ken	✓ Safety	Maatling
			495	Harbec	✓	
			804	Kei Det	✓	

JOB TYPE Long String HOLE SIZE 5 7/8" HOLE DEPTH 720' CASING SIZE & WEIGHT 2 7/8" EVE  
CASING DEPTH 607' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
DISPLACEMENT 4.03 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 200# Bentonite followed by 5 bbls fresh water, mixed & pumped 67 sks Thixoblend II cement w/ 1# Phenoseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MIT, released pressure to set float valve.

\* Customer supplied H<sub>2</sub>O

*[Handwritten signature]*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ CE0450	1	PUMP CHARGE	1500.00	
✓ CE0002		MILEAGE		
✓ CE0711	1/3 min	low mileage	220.00	
		trucks	1720.00	
		-45%	774.00	
		Subtotal		946.00 ✓
silva ✓ CC58611	67 sks	Thixoblend II cement	1809.00	
✓ CC5965	200 #	Bentonite	60.00	
✓ CC6079	67 #	Phenoseal	70.45	
✓ CP8776	1	2 1/2" rubber plug	45.00	
		materials	2004.45	
		-45%	902.00	
		Subtotal		1102.45 ✓
		8%	SALES TAX	88.20
		ESTIMATED TOTAL		2136.65
		DATE		(3887.81)

RAVIN 3737  
AUTHORIZATION J.R. TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.