



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

100846
41044

INV901189

TICKET NUMBER 55623 ✓
LOCATION Chanute, KS
FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/30/19	4015	Wingert # I-2	NW 9	17	22	MI
CUSTOMER JTC Oil Inc. ✓			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 35790 Plum Creek Rd			729	Casey	✓	
CITY STATE ZIP CODE Osawatimie KS 66064			495	HarBec	✓	
			804	KaiDet	✓	

JOB TYPE longstring HOLE SIZE 5 7/8" HOLE DEPTH 740' CASING SIZE & WEIGHT 2 7/8" EUE
CASING DEPTH 725' DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT 4.20 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safely meeting, established circulation, mixed & pumped 200#
Bentonite followed by 5 bbls fresh water, mixed & pumped 70 sks
Thixoblend II cement w/ 1# Phenoseal per sk, cement to surface,
flushed pump clean, pumped 2 1/2" rubber plug to casing TP w/ 4.20 bbls
bbls fresh water, pressured to 800 PSI, well held pressure for 30 min
MIT, released pressure to set float valve.

* Customer supplied H₂O

[Handwritten signature]

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ CE0450	1	PUMP CHARGE	1500.00	
✓ CE0002	20 mi	MILEAGE	143.00	
✓ CE0711	1/3 mi	ten mileage	220.00	
		trucks	1863.00	
		- 45%	838.35	
		subtotal		1024.65 ✓
✓ CC5861	70 sks	Thixoblend II cement	1890.00	
✓ CC5965	200 #	Bentonite	60.00	
✓ CC6079	70 #	Phenoseal	94.50	
✓ CP8176	1	2 1/2" rubber plug	45.00	
		materials	2089.50	
		- 45%	940.28	
		subtotal		1149.22 ✓
		8%		
		SALES TAX		71.94
		ESTIMATED TOTAL		2265.81
		DATE		(4/19/20)

Ravin 3737

AUTHORIZATION *[Signature]* TITLE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.