

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009

**Type or Print on this Form**  
**Form must be Signed**  
**All blanks must be Filled**

OPERATOR: License #: \_\_\_\_\_  
 Name: \_\_\_\_\_  
 Address 1: \_\_\_\_\_  
 Address 2: \_\_\_\_\_  
 City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_ + \_\_\_\_\_  
 Contact Person: \_\_\_\_\_  
 Phone: ( \_\_\_\_\_ ) \_\_\_\_\_  
 Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - \_\_\_\_\_  
 Spot Description: \_\_\_\_\_  
 \_\_\_\_\_ - \_\_\_\_\_ - \_\_\_\_\_ - \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
 \_\_\_\_\_ Feet from  North /  South Line of Section  
 \_\_\_\_\_ Feet from  East /  West Line of Section  
 Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
 County: \_\_\_\_\_  
 Lease Name: \_\_\_\_\_ Well #: \_\_\_\_\_  
 Date Well Completed: \_\_\_\_\_  
 The plugging proposal was approved on: \_\_\_\_\_ (Date)  
 by: \_\_\_\_\_ (KCC District Agent's Name)  
 Plugging Commenced: \_\_\_\_\_  
 Plugging Completed: \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugging Contractor License #: \_\_\_\_\_ Name: \_\_\_\_\_  
 Address 1: \_\_\_\_\_ Address 2: \_\_\_\_\_  
 City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_ + \_\_\_\_\_  
 Phone: ( \_\_\_\_\_ ) \_\_\_\_\_  
 Name of Party Responsible for Plugging Fees: \_\_\_\_\_  
 State of \_\_\_\_\_ County, \_\_\_\_\_, ss.  
 \_\_\_\_\_  Employee of Operator or  Operator on above-described well,  
 (Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

**Submitted Electronically**

# QUALITY WELL SERVICE, INC.

7196

Federal Tax I.D. # 481187368

Home Office 30060 N. Hwy 281, Pratt, KS 67124

Mailing Address P.O. Box 468

Office 620-727-3410

Fax 620-672-3663

Rich's Cell 620-727-3409

Brady's Cell 620-727-6964

Date	Sec.	Twp.	Range	County	State	On Location	Finish
8-13-19	10	29S	23W	Foro	Ks		
Lease <i>102line</i>	Well No. <i>1-10</i>		Location <i>Kingdom, Ks, W to Wilbourn Rd W to 122<sup>nd</sup></i>				
Contractor <i>Duke Delg Rig #1</i>				Owner <i>15 to Wildlife 1/4 W S. 10</i>			
Type Job <i>8 3/8</i>				To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.			
Hole Size <i>12 1/4</i>	T.D. <i>690'</i>		Charge To <i>Vincent Oil Corp</i>				
Csg. <i>8 3/8 23</i>	Depth <i>688'</i>		Street				
Tbg. Size	Depth		City				
Tool	Depth		State				
Cement Left in Csg.	Shoe Joint <i>42.23</i>		The above was done to satisfaction and supervision of owner agent or contractor.				
Meas Line	Displace <i>41 1/2</i>		Cement Amount Ordered <i>1255 max 3 1/2 CC 1/2 PS</i>				
<b>EQUIPMENT</b>				<i>1305 Common 2 1/2 CC 3 1/2 CC 1/2 PS</i>			
Pumptrk <i>8</i> No. <i>TJ</i>				Common <i>1509</i>			
Bulktrk <i>10</i> No. <i>Tom</i>				Poz. Mix <i>1255</i>			
Bulktrk <i>15</i> No. <i>Jake</i>				Gel. <i>561 1/2</i>			
Pickup No.				Calcium <i>776 1/2</i>			
<b>JOB SERVICES &amp; REMARKS</b>				Hulls			
Rat Hole				Salt			
Mouse Hole				Flowseal <i>137.5 1/2</i>			
Centralizers				Kol-Seal			
Baskets				Mud CLR 48			
D/V or Port Collar				CFL-117 or CD110 CAF 38			
<i>Run 16 3/8 2 1/2 CC 3 1/2 CC 1/2 PS 689'</i>				Sand			
<i>STARTS Csg. 680' Bottom that up to</i>				Handling <i>293</i>			
<i>csg + Break csg wire</i>				Mileage <i>160 / 900</i>			
<i>small Pumping 10 1/2 1/2</i>				<b>FLOAT EQUIPMENT</b>			
<i>START MIX + Pump 1255 max 3 1/2 CC 1/2 PS</i>				Guide Shoe <i>8 3/8 Baffle Plate 1EA</i>			
<i>12 1/2 hpl</i>				Centralizer <i>8 3/8 Wooden Plug 1EA</i>			
<i>START MIX + Pump 1505 Common</i>				Baskets			
<i>2 1/2 CC 3 1/2 CC 1/2 PS 14.8 hpl</i>				AFU Inserts			
<i>plug down Release 8 3/8 Wooden Plug</i>				Float Shoe			
<i>START 1160</i>				Latch Down <i>1 EA</i>			
<i>plug down 41 1/2 out</i>				Service Sps <i>1EA</i>			
<i>450" Close valve on csg</i>				LMI <i>60</i>			
<i>1700 csg thru 103</i>				Pumptrk Charge <i>surface</i>			
<i>csg cut to pit</i>				Mileage <i>180</i>			
<i>Thank you</i>				Tax			
<i>Please call again</i>				Discount			
<i>7000</i>				Total Charge			
<i>12/23/19</i>							
Signature <i>[Handwritten]</i>							



PEA

PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1004433	1718	08/23/2019
<b>INVOICE NUMBER</b>			
<b>93034911</b>			

Pratt (620) 672-1201  
 B VINCENT OIL CORPORATION  
 I 200 WEST DOUGLAS STE 725  
 L WICHITA  
 L KS US 67202  
 T  
 O ATTN: BRYAN HILLS

J LEASE NAME TORLINE 1-10  
 O LOCATION  
 B COUNTY FORD  
 S STATE KS  
 I JOB DESCRIPTION Cement-New Well Casing/Pi  
 T JOB CONTACT  
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41187894			Net - 30 days	09/22/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<b>For Service Dates: 08/22/2019 to 08/22/2019</b>				
0041187894				
171819652L Cement-New Well Casing/Pi 08/22/2019				
<b>PLUG TO ABANDON</b>				
170 SK-60/40 Poz	1.00	SK	2,174.30	2,174.30 T
320 LB-Cement Gel	1.00	LB	89.60	89.60 T
Heavy Equiprnt Mileage	140.00	MI	4.40	616.00
Blending & Mixing Service Charge	170.00	SK	0.77	130.90
Ton Mileage	560.00	MI	1.65	924.00
Depth Charge, 1001'-2000'	1.00	HR	825.00	825.00
Light Vehicle Mileage	70.00	MI	2.75	192.50
Service Supervisor Charge	1.00	EA	75.00	75.00
Driver Charge	1.00	EA	35.00	35.00

<b>PLEASE REMIT TO:</b>	<b>SEND OTHER CORRESPONDENCE TO:</b>	<b>SUB TOTAL</b>	<b>5,062.30</b>
<b>BASIC ENERGY SERVICES, LP</b>	<b>BASIC ENERGY SERVICES, LP</b>	<b>TAX</b>	<b>173.19</b>
<b>PO BOX 841903</b>	<b>801 CHERRY ST, STE 2100</b>	<b>INVOICE TOTAL</b>	<b>5,235.49</b>
<b>DALLAS, TX 75284-1903</b>	<b>FORT WORTH, TX 76102</b>		

DEA



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

**PRESSURE PUMPING Job Log**

Customer:	Vincent Oil	Cement Pump No.:	38117, 19919 2Hrs.	Operator TRK No.:	98816
Address:		Ticket #:	1718 19652 L	Bulk TRK No.:	14354, 19808 Cory
City, State, Zip:		Job Type:	Z42 - Plug to Abandon		
Service District:	1718 - Liberal, Ks.	Well Type:	OIL		
Well Name and No.:	Torline 1-10	Well Location:	10,29,23	County:	Ford
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
60/40 Poz	170		14354, 19808 Cory	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Tail:	14.8	1.32	6.31	224.4	TT Man Hours:	22
					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
10:45							ON LOCATION & SAFETY MEETING
11:00							RIG UP
11:39 AM		11.7 slurry					PUMP 50SX TAIL @ 14.8# / 1630'
11:44 AM		20.3					DISPLACE W/ MUD 20.3BBL
12:13 PM		11.7 slurry					PUMP 50SX TAIL @ 14.8# / 720'
12:15		7.3					DISPLACE W/ 7.3BBL
12:45		4.6 slurry					PUMP 20SX @ 14.8# / 60'
12:46 PM							SHUTDOWN / CEMENT TO SURFACE
12:52		11.7 slurry					PLUG RAT & MOUSE W/ 50SX
13:00							SHUTDOWN
							JOB COMPLETE

Size Hole	Depth	New / Used		TYPE	Swage		
Size & Wt. Csg.	8 5/8" 24#	Depth		Packer	Depth		
Drill P.	4 1/2" 16.6#	Depth		Plugs	Rat & Mouse	Depth	
Top Plugs		Type		Plugs	1630'	720'	60'

Customer Signature: *[Signature]* Basic Representative: Daniel Beck  
 Basic Signature: *[Signature]*  
 Date of Service: 8/22/2019