

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4

March 2009

Type or Print on this Form

Form must be Signed

All blanks must be Filled

OPERATOR: License #: 33192
Name: Crown Energy Company
Address 1: 1117 N.W. 24TH ST.
Address 2: _____
City: OKLAHOMA CITY State: OK Zip: 73106 + 5615
Contact Person: Jess Eastwood
Phone: (405) 526-0111
Type of Well: (Check one) ☐ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☒ ENHR Permit #: E25918.2 ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-015-40330-00-00
Spot Description: _____
NE SW SW NE Sec. 17 Twp. 29 S. R. 8 ☒ East ☐ West
3061 Feet from ☐ North / ☒ South Line of Section
2299 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Butler
Lease Name: WEHRMAN Well #: 6
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 10/19/2019
Plugging Completed: 11/4/2019

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Drove to location, rigged up, unhooked well head, drove in.
Drove to location, pulled on tubing, tubing was plaited 50 joints down, pulled tubing out, dug cellar and pit, put liner in pit, and put fence up around pit.
Drove to location, set up to wash over, ran wash pipe and tubing to 1555' washed over 5', had pump issues, drove to hotel.
Drove to location, had Kansas Fishing Tool bring mud pump out, washed over tubing to 1945; pulled tubing out, drove home.
Drove to location, ran in wash pipe and tubing and tubing cutter to 1945' cut tubing, came out with 385' of tubing, cut joint off with torch, ran tubing back into 1945'.
Drove to location, washed over to 2345' pulled tubing out, ran cutter and wash pipe and tubing to top, drove to hotel.
Drove to location, ran tubing to 2345', cut tubing off, pulled out 390' of tubing, cut off tubing with torch, washed over to packer, pulled tubing out to wash pipe, drove to hotel.
Drove to location, pulled wash pipe out, put tubing cutter on, ran in, cut tubing off, knocked packer to bottom of hole, came out with last of tubing, cut tubing off with torch, rail tubing to 2538', pumped 35 sacks cement, 100# hulls, 3% ec, pulled tubing to 2200', drove home.
Drove to location, didn't tag plug, pumped 35 sacks cement, 3% ec, 100# hulls, pulled tubing to 2200', pumped 35 sacks cement, pulled tubing to 1850', pumped 35 sacks cement, pulled tubing to 1400', pumped 35 sacks cement, pulled tubing to 2500' pumped 35 sacks cement, pulled tubing out, topped off with 20 sacks cement, cut well off 4' below ground, topped off with 15 sacks cement, tore down rig, filled pit and cellar in.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc.
Address 1: 190 US HWY 56 Address 2: _____
City: ELLINWOOD State: KS Zip: 67526 + 8911
Phone: (620) 727-3410

Name of Party Responsible for Plugging Fees: Crown Energy

State of _____ County, _____, ss.

(Print Name)

☐ Employee of Operator or ☐ Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically