

Elite Cementing & Acidizing of KS, LLC
 810 E 7th, PO Box 92
 Eureka, KS 67045



Date	Invoice #
9/11/2017	3516

Bill To	
Val Energy Inc. 125 N. Market St., Suite 1110 Wichita, KS 67202	
Customer ID#	1217

Job Date	9/8/2017
Lease Information	
Thelma 1-24	
County	Cowley
Foreman	KM

Item	Description	Qty	Terms	Net 15
			Rate	Amount
C102	Cement Pump-Longstring	1	1,050.00	1,050.00
C107	Pump Truck Mileage (one way)	60	3.95	237.00
C201	Thick Set Cement	160	19.50	3,120.00T
C207	KolSeal	800	0.45	360.00T
C208	Pheno Seal	320	1.25	400.00T
C108B	Ton Mileage-per mile (one way)	528	1.35	712.80
C421	5 1/2" Latch Down Plug	1	230.00	230.00T
C752	5 1/2" Type A Packer Shoe (7 3/4 x 8)	1	1,400.00	1,400.00T
C681	5 1/2" Float Collar Body Only	1	225.00	225.00T
C604	5 1/2" Cement Basket	1	225.00	225.00T
C504	5 1/2" Centralizer	6	48.00	288.00T
C790	Thread Lock Kit	1	30.00	30.00T
D101	Discount on Services		-99.99	-99.99
D102	Discount on Materials		-313.90	-313.90T

We appreciate your business!

Phone #	Fax #	E-mail
620-583-5561	620-583-5524	rene@elitecementing.com

Send payment to:
 Elite Cementing & Acidizing of KS, LLC
 PO Box 92
 Eureka, KS 67045

Subtotal	\$7,863.91
Sales Tax (6.75%)	\$402.58
Total	\$8,266.49
Payments/Credits	\$0.00
Balance Due	\$8,266.49

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 3516
 Foreman Kevin McCoy
 Camp EUREKA

API # 15-035-23485-00-01

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-8-17	1217	Thelma 1-24	24	325	SE	Cowley	Ks
Customer <u>VAL Energy Inc.</u>		Safety Meeting LM D6 AM	Unit #	Driver	Unit #	Driver	
Mailing Address <u>125 N. MARKET ST. STE 1110</u>			105	DAVE G.			
City <u>Wichita</u>			112	ALAN M.			
State <u>Ks</u>	Zip Code <u>67202</u>						

Job Type Longstring Hole Depth 3600' KB Slurry Vol. 44 BBL Tubing _____
 Casing Depth 3543.50' G.L. Hole Size 7 7/8 Slurry Wt. 13.8** Drill Pipe _____
 Casing Size & Wt. 5 1/2 15.50** Cement Left in Casing 3.50' Water Gal/SK 9.0 Other _____
 Displacement 85.5 BBL Displacement PSI 700 Bump Plug to 1200 PSI BPM _____

Remarks: Safety Meeting: Rig up to 5 1/2 casing. Drop BRASS TRIP BALL. Set PACKER Shoe @ 1500 PSI. Pump 10 BBL Fresh water. Mixed 135 SKS THICK Set Cement w/ 5* KOL-SEAL /SK, 2* PHENOSEAL /SK @ 13.8*/GAL yield 1.82 = 44 BBL Slurry. Wash out Pump & Lines. Shut down. Release LATCH down Plug. Displace Plug to Seat w/ 85.5 BBL Fresh water. FINAL Pumping Pressure 700 PSI. Bump Plug to 1200 PSI. wait 2 mins. Release Pressure. FLOAT & Plug Heild. Good CIRCULATION @ ALL times while Cementing Job Complete. Rig down.

Plug Rate Hole & Mouse hole

CENTRALIZERS ON #13, 5, 7, 9, 11 BASKET ON TOP OF #12

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	60	Mileage	3.95	237.00
C 201	160 SKS	THICK Set Cement	19.50	3120.00
C 207	800 #	KOL-SEAL 5*/SK	.45#	360.00
C 208	320 #	PHENOSEAL 2*/SK	1.25#	400.00
C 108B	8.8 TONS	TON Mileage 60 miles	1.35	712.80
C 421	1	5 1/2 LATCH down Plug	230.00	230.00
C 752	1	5 1/2 Type A PACKER Shoe	1400.00	1400.00
C 681	1	5 1/2 FLOAT Collar Body only	225.00	225.00
C 604	1	5 1/2 Cement BASKET	225.00	225.00
C 504	6	5 1/2 x 7 7/8 CENTRALIZERS	48.00	288.00
C 790	1	THREAD Lock Kit	30.00	30.00
			Sub Total	8277.80
			Less 5%	435.08
			Sales Tax 6.75%	423.77
Authorization <u>Rick Smith</u> Title _____			Total	8266.49

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.