



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

**PRESSURE PUMPING**

**Job Log**

Customer:	Raydon Exploration	Cement Pump No.:	38117-19919 10HRS	Operator TRK No.:	78939
Address:	1601 NW Expressway STE 1300	Ticket #:	1718-14493 L	Bulk TRK No.:	37723-37725 30463-37547
City, State, Zip:	OKC OK 73118	Job Type:	Z42 - Cement Production Casing		
Service District:		Well Type:	OIL		

Well Name and No.:	Linda Jo 1-22	Well Location:	22,33,31	County:	Seward	State:	Ks
--------------------	---------------	----------------	----------	---------	--------	--------	----

Type of Cmt	Sacks	Additives	Truck Loaded On		
A-CON	150	1/4# POLYFLAKE	37723-37725	Front	Back
AA-2	275	5%W-60, 10%SALT, 6%C-15, 1/4#DEFOAMER, 5#GILSONITE	30463-37547	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
<b>Lead:</b>	11.4	2.95	18.1	442.5	Man Hours:	45
<b>Tail:</b>	14.8	1.51	6.64	415.25	# of Men on Job:	4

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
21:30							ON LOC, SAFTEY MTG, R.U.
5:35						4000	TEST LINES
5:41 AM	3	10				230	PUMP MUD FLUSH
5:44 AM	3	5				230	H2O SPACER
5:51 AM							PLUG RAT & MOUSE
6:04	7.5	53				480	START LEAD @ 11.4#
6:12	7.4	74				200	ON TAIL @ 14.8#
6:25 AM							SHUT DOWN, WASHUP, DROP PLUG
6:32	6.5					110	START DISPLACEMENT
6:53	2	132				660	SLOW RATE
6:58		141				800-1260	PLUG DOWN
7:00						1260-0	RELEASE PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	7 7/8	Depth	5980'		TYPE	
Size & Wt. Csg.	5 1/2 15.5	Depth	5989	New / Used	Packer	Depth
tbg.		Depth			Retainer	Depth
Top Plugs		Type			Perfs	CIBP

Customer Signature:	Basic Representative:	CHAD HINZ
	Basic Signature:	
	Date of Service:	8/12/2017