

JOB LOG

SWIFT Services, Inc.

DATE 10-24-19 PAGE NO. 1

CUSTOMER Hess Oil Co WELL NO. #2 LEASE Griss JOB TYPE PTA TICKET NO. 032857

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	

	0830							On Location tbg 2 3/8 x 5 1/2" csg
--	------	--	--	--	--	--	--	------------------------------------

	0900	1/2	2.5		✓		300	Plug 8 5/8 w/ 10 sks 60/40 Poz 4% gel
	0910	4	10	✓		100		Pump 10 bbl H2O spacer

	0915	4	25	✓		500		Pump 10 sks of Gel
--	------	---	----	---	--	-----	--	--------------------

	0930	3 1/2	17	✓		450		143 JTS tbg Plug @ 4406' w/ 65 sks of 60/40 Pozmix 4% gel + 200# hulls @ 13/ppg
								Pull 79 J to tbg

	1115	3 1/2	25	✓		400		Plug @ 1975' w/ 95 sks 60/40 4% gel + 200# Cotton Seed Hulls - Pull 31 Joints
--	------	-------	----	---	--	-----	--	--

	1200	3 1/2	33	✓		300		Plug @ 1,000' w/ 125 sks + 200# of Hulls ★ Circulate CMT to Surface ★
--	------	-------	----	---	--	-----	--	--

TOH, pull rest of tbg

	1300	1/2	3	✓		0		Top off 5 1/2" w/ 15 sks
--	------	-----	---	---	--	---	--	--------------------------

	1330							Wash up Trk #112 + contractor's equip Job Complete
--	------	--	--	--	--	--	--	---

310 sks of 60/40 Pozmix 4% gel w/ 600# of Hulls used

Thank You  
GIDSON, PRESTON, ISAAC