



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

15-19-31

FIELD SERVICE TICKET
1718 17875 A

DATE _____ TICKET NO. _____

DATE OF JOB <u>6/26/2019</u> DISTRICT <u>Pratt, KS</u>				NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/> PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/> CUSTOMER ORDER NO.:			
CUSTOMER <u>LD Drilling</u>				LEASE <u>Romsy Trust</u>		WELL NO. <u>15B#1</u>	
ADDRESS				COUNTY <u>Scott</u>		STATE <u>KS</u>	
CITY STATE				SERVICE CREW <u>Darin, Brett, Digz</u>			
AUTHORIZED BY				JOB TYPE: <u>24 2 1/2 Longstring</u>			
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE <u>6/24</u> AM <u>12:30</u> TIME
<u>19843</u>	<u>1</u>					ARRIVED AT JOB	<u>6/24</u> AM <u>6:30</u>
<u>19860</u>	<u>1/2</u>					START OPERATION	<u>6/24</u> AM <u>10:30</u>
						FINISH OPERATION	<u>6/24</u> PM <u>11:30</u>
						RELEASED	<u>6/24</u> PM <u>12:00</u>
						MILES FROM STATION TO WELL	<u>170</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: Ruby Papp
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT	
BC145	Dr2 Cement Premium	SK	150		2,850 00	
BC132	60/40 Poz	SK	30		810 00	
CC102	Cellofiske	Lb	35		152 00	
CC105	C-41 P	Lb	71		284 00	
CC111	S914	Lb	815		467 50	
CC113	Gypsum	Lb	705		218 55	
CC187	C-17	Lb	92		2,208 00	
CC201	Gilsonite	LB	901		901 00	
CC133	KCL	Gal	5		365 00	
CC151	Mud Flush	Gal	1,000		1,500 00	
ME101	Light Vehicle Mileage	MI	100		500 00	
ME102	Heavy Equipment Mileage	MP	200		1,600 00	
CC5	Depth Charge, 4,000' - 5,000'	HR	1		2,500 00	
CE240	Blending & Mixing Service Charge	SK	180		252 00	
CF851	5 1/2 FLOST Shoe (Blue)	ES	1		425 00	
CF607	Lower Down Plug & Baffle, 5 1/2 (Blue)	ES	1		400 00	
CF1901	5 1/2 Basket (Blue)	ES	2		580 00	
CF1651	Turbolizers, 5 1/2 (Blue)	ES	12		1,320 00	
CF481	5 1/2" Port Collar	ES	1		3,500 00	
BE143	Supervisor Charge	EA	1		75 00	
BE144	Driver Charge	EA	1		105 00	
					SUB TOTAL	20,955 05

CHEMICAL/ACID DATA:			

SERVICE & EQUIPMENT	%TAX ON \$	
MATERIALS	%TAX ON \$	
Discounted TOTAL		14,721 14

SERVICE REPRESENTATIVE Darin Fulkerson THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: Ruby Papp
(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.

Customer LD Drilling	Lease No.	Date 6/26/2019
Lease Rmsy Trust	Well # 15B-1	
Field Order # 17875	Station PRATT KS	Casing 5 1/2
		Depth 4681
Type Job 242/5 1/2 long string	Formation TD-4690	Legal Description 15-19-31
		County Scott
		State KS

PIPE DATA		PERFORATING DATA		FLUID USED	TREATMENT RESUME		
Casing Size	Tubing Size	Shots/Ft		Acid	RATE	PRESS	ISIP
5 1/2							
Depth 4681	Depth	From	To	Pre Pad	Max		5 Min.
Volume 111.4	Volume	From	To	Pad	Min		10 Min.
Max Press 1500	Max Press	From	To	Frac	Avg		15 Min.
Well Connection	Annulus Vol.	From	To		HHP Used		Annulus Pressure
Plug Depth 4685	Packer Depth	From	To	Flush KCL wster	Gas Volume		Total Load

Customer Representative Rick Pupp	Station Manager Justin Westerman	Treater Darin Froneman
Service Units 72911	78982	19843
19860	19860	
Driver Names Darin	Brett	Brett
D,92	D,92	

Time	Casing Pressure	Tubing Pressure	Bbbls. Pumped	Rate	Service Log
6:30pm					On Location / Safety meeting
					150 SK PA2 Premium Cement, 10% S91+
					10% Gypsum, 6# G. Isocure, - 5% Fluid Loss
					- 5% Defoamer, - 25# Cellulose
					14.8 ppg, 1.54 vels, 6.52 wster
10:30pm	300		5	5	Pump 5 bbls wster
	300		24	5	Pump 24 bbls mix Flush
	300		5	5	Pump 5 bbls wster
	300		41	6	mix 150 SK PA2
					shut down
					Wash pump & lines
					Release Plug
	200		0	6	Start displacement
	400		85	6	Li-ft Pressure
	500		101	3	Slow Rate
10:24pm	1500		110	3	Bump Plug
					Flow - Held
	0		7	3	Plug Rat hole - 30SK 60/100 Poz 4% Gm
11:30pm					Job Complete / Darin crew
					Thank you!!!