

Customer LD Drilling	Lease No.	Date 8-13-19
Lease POTTER	Well # 1-6	
Field Order # 18039	Station Pratt	Casing 8 5/8
Type Job 2-42-Su	Formation	Depth
		County NESS
		State KS
		Legal Description 6-185-24w

PIPE DATA		PERFORATING DATA		FLUID USED		TREATMENT RESUME		
Casing Size 8 5/8	Tubing Size	Shots/Ft		Acid 290 SAs 60/40 POZ	RATE	PRESS	ISIP	
Depth 345.6	Depth	From	To	Pre Pad	Max		5 Min.	
Volume 21.9	Volume	From	To	Pad	Min		10 Min.	
Max Press 300	Max Press	From	To	Frac	Avg		15 Min.	
Well Connection 3V	Annulus Vol.	From	To		HHP Used		Annulus Pressure	
Plug Depth 325	Packer Depth	From	To	Flush 20.7	Gas Volume		Total Load	

Customer Representative Rich	Station Manager Westerman	Treater MATTW
Service Units 98258	84981	20920
Driver Names MATTW	MARQUEZ	STEVE
	70959	19860

Time	Casing Pressure	Tubing Pressure	Bbbs. Pumped	Rate	Service Log
8:50					ON location / safety meeting
12:10					RUN 8 5/8 CASING
12:55					CSNG ON BOTTOM
1:05					HOOK TO CSNG / BREAK CIRC W. RIG
1:10	100		3	4	PUMP 3 bbl WATER
1:12	100		62	4	MIX 290 SAs 60/40 POZ
1:35	150			4	START displacement
1:45	175		20.7		plug down / shut in well
					CEMENT TO SURFACE

JOB COMPLETE
 THANK YOU!
 MIKE MATTW
 EDMUNDO + STEVE