





Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

**PRESSURE PUMPING Job Log**

Customer:	LD Drilling	Cement Pump No.:	38750-19842 <i>4hrs</i>	Operator TRK No.:	96815
Address:		Ticket #:	1718-19730 L	Bulk TRK No.:	84891-19862
City, State, Zip:		Job Type:	Z42 - Plug to Abandon		
Service District:		Well Type:	OIL		
Well Name and No.:	Potter 1-6	Well Location:	6,18,24	County:	Ness
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
60/40 POZ	230	4%GEL, 1/4#POLYFLAKE	84891-19862	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
<b>Lead:</b>	14.8	1.21	5.18	278.3	Man Hours:	27
<b>Tail:</b>					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
11:00							ON LOC, SAFTEY MTG, R.U.
11:39	6	10			190		H2O SPACER
11:56 AM	5.5	10.7			200		MIX 50 SX @ 1680'
11:59 AM	3.5	3			40		H2O SPACER
12:01 PM	6	18					MUD
12:41	5	10			120		H2O SPACER
12:44	5	17.2			120		MIX 80 SX @ 900'
12:49 PM	5	8			30		H2O DISPLACEMENT
13:19	5	10			50		H2O SPACER
13:22	5	10.7			50		MIX 50 SX @ 360'
13:24	5	2					DISPLACE
14:16	3	4.3					MIX 20 SX @ 60'
14:23	3	6.4					PLUG RAT HOLE
							WASHUP
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!

Size Hole	Depth			TYPE	
Size & Wt. Csg.	Depth		New / Used	Packer	Depth
lbg.	Depth			Retainer	Depth
Top Plugs	Type			Perfs	CIBP

Customer Signature: <i>[Signature]</i>	Basic Representative:	CHAD HINZ
	Basic Signature:	<i>[Signature]</i>
	Date of Service:	8/31/2019

LD DRILLING  
POTTER 1-6

