

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4618**
 Foreman David Gardner
 Camp Eureka

API# 15-035-24708

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
8-6-19	1273	Olsen #18-1	18	35 S.	7E.	Cowley	KS	
Customer McGowan Oil Company			Unit #		Driver		Unit #	Driver
Mailing Address 302 N. Summit			105		Jason			
City Arkansas City			113		Tosh			
State KS		Zip Code 67005						

Job Type Plug New Well Hole Depth 3100' Slurry Vol. Bbl Total Tubing _____
 Casing Depth _____ Hole Size 7 7/8" Slurry Wt. 14" Drill Pipe 4 1/2" 16.60"
 Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK 6.5 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 4 1/2" Drill pipe. Plug well as follows:

35 SKS @ 382'
25 SKS @ 60' to Surface
15 SKS in Rat hole
15 SKS in Mouse hole
90 SKS Total

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C103	1	Pump Charge	1100.00	1100.00
C107	70	Mileage	4.20	294.00
C203	90 SKS	60/40 Pozmix Cement	13.40	1206.00
C206	310 [#]	Gel @ 4%	.21	65.10
C488	3.37 Tons	Ton Mileage - Bulk Truck	1.90	379.26
<u>Thank You</u>				
			Sub Total	3,044.36
			Less 5%	156.35
			Sales Tax	82.62

Authorization by Charlie Coulter Title Lighthouse Drilling Contractor Total 2,970.63

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4643**
 Foreman KEVIN MCGAY
 Camp EUREKA

API # 15-035-24708-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
8-2-19	1273	Olsen #18-1	18	35S	7E	Cowley	Ks	
Customer McGOWAN OIL COMPANY			Safety Meeting KM AM CG		Unit #	Driver	Unit #	Driver
Mailing Address 302 N. Summit					104	ALAN M.		
City ARKANSAS CITY					112	CALEB G.		
State Ks		Zip Code 67005						

Job Type SURFACE Hole Depth 343' K.B. Slurry Vol. _____ Tubing _____
 Casing Depth _____ Hole Size 12 1/4" Slurry Wt. 15" Drill Pipe _____
 Casing Size & Wt. 8 5/8" 23" Cement Left in Casing 20' Water Gal/SK _____ Other _____
 Displacement 20.7 BBL Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY MEETING: Rig up to 8 5/8" casing. BREAK CIRCULATION w/ 10 BBL fresh water. Mixed 175 SKS CLASS 'A' Cement w/ 3% CaCl2, 2% Gel, 1/4" FloSeal/SK @ 15#/gal = 42 BBL slurry. Displace w/ 20.7 BBL fresh water. Shut casing in. No cement to surface. CALL FOR MORE cement & 1" tubing.

Ran & wash down 1" Hydrill tubing. Tag firm cement @ 31' below G.L. Mixed 55 SKS CLASS 'A' Cement w/ 3% CaCl2, 2% Gel, 1/4" FloSeal/SK. Good cement to surface. full 1". Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 151	1	Pump Charge	890.00	890.00
C 157	70	Mileage	4.20	294.00
C 200	130 SKS	CLASS 'A' Cement	15.75	3622.50
C 205	650 #	CaCl2 3%	.63 #	409.50
C 206	430 #	Gel 2%	.21 #	90.30
C 209	55 #	FloSeal 1/4" /SK	2.35 #	129.25
C 200	10.51 Tons	Ton Mileage 70 miles	1.40	1059.38
			Sub Total	6494.93
			Less 5%	338.56
			Sales Tax	276.35
			Total	6432.72

THANK YOU

Authorized By Charles Gault

Title Light House Drilling Contractor

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.