




Dale Jackson Production Co.
 Box 266, Mound City, Ks 66056
 Cell # 620-363-2683



Well #: 5-19
Location: NENESESWS18T17SR24E
County: Miami
FSL: 1223
FEL: 2864
API#:15-121-31611
Started: 11-13-2019
Completed: 11-14-2019

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"	SN: ----	TD: 377'	Packer: ----
Longstring: ----	Cemented: 65 sacks PLUGGED	Hole Size: 5 5/8	Plugged: ----	Bottom Plug: ----	

Lease:	Spindle
Owner:	Bobcat Oilfield Services
OPR #:	3895
Contractor:	DALE JACKSON PRODUCTION CO.
OPR #:	4339

Well Log

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
2	2	Top Soil	4	370	Sandy Shale (Poor Bleed) (Oil Sand Streak)
5	7	Clay	TD	377	Shale
10	17	Lime			
1	18	Black Shale			
3	21	Lime			
7	28	Sand			
4	32	Lime			
20	52	Shale			
3	55	Lime			
18	73	Shale			
2	75	Oil Sand (Some Shale) (Poor bleed)			
5	80	Oil Sand (Very Shaley) (Fair bleed)			
3	83	Oil Sand (Fair Bleed) (Some Shale)			
2	85	Oil Sand (Very Shaley) (Poor Bleed)			
1	86	Sand Shale (Oil Sand Streak)			
15	101	Shale			
13	114	Lime			
13	127	Shale			
27	154	Lime			
3	157	Shale			
2	159	Black Shale			
4	163	Light Shale (Limey)			
19	182	Lime			
3	185	Black Shale			
7	192	Lime			
2	194	Shale			
3	197	Lime			
14	211	Shale Light (Limey)			
9	220	Sandy Shale			
16	236	Sand (No odor)			Surface 20' of 6"
44	280	Sandy Shale			Set Time 2:00PM 11/13/2019
40	320	Shale			Called 1:02PM Brooke
16	336	Light Shale			Well Plugging 11/14/2019 TD-Surface
10	346	Shale			Called 1:30PM Brooke TD 377'
5	351	Black Shale			DRY HOLE
4	355	Light Shale			
1	356	Sandy Shale			
1	357	Oil Sand (Very Shaley) (Poor bleed)			
1	358	Oil Sand (Limey) (Poor bleed)			
1	359	Shale & Lime (Slight Oil Show)			
1	360	Lime			
2	362	Oil sand (Very Shaley) (Poor bleed)			
4	366	Sandy Shale (No Oil)			



Dale Jackson Production Co.
Box 266, Mound City, Ks 66056
Cell # 620-363-2683
Office # 620-363-2696

