

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4839**
 Foreman Russell McLow
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-20-19	1313	CANNON # 4				Butler	KS
Customer			Safety Meeting	Unit #	Driver	Unit #	Driver
MwK Petroleum Co.				102	Zevi		
Mailing Address				115	Russ		
508 Stone Lake Co				114	Steve		
City				128	Greg		
Augusta							
State	Zip Code						
KS	67010						

Job Type P.T.A. Old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8
 Casing Depth _____ Hole Size WV K casing (Big) Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 7" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI 200# Bump Plug to _____ BPM 3 1/2

Remarks: Safety Meeting + Job Procedure 2 3/8 set @ 660'
SPOT 35 SKs Reg 2% Gel 2 1/2 CC w/ Hull's wait 1 1/2 hr TAG @ 630 = 30 FT Fill
SPOT 50 SKs Reg 2% Gel 2 1/2 CC w/ Hull's wait 1 1/2 hr TAG @ 620 = 10 FT Fill
SPOT 65 SKs Reg 2% Gel 2 1/2 CC w/ Hull's wait 1 1/2 hr TAG @ 288 = 332 FT Fill
PSF TEST 7" to 300# GOOD TEST PERF 4 Holes @ 250'
Rig to 7" Break circulation, mix + Pump 185 60/40 SKs 60/40 Pozmix
Fill 7" INSIDE + OUT w/ cement well stayed Full. Job complete TRADOWN.

NOTE 335 SKs TOTAL Thank you
Russell McLow

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	785.00	785.00
C-107	10	Mileage From EIDorado	420	420.00
C-200	150	SKs CLASS A Reg) Bottom	15.75	2,362.50
C-205	350#	CAC12) Plug	63	220.50
C-214	45#	Hull's	50	22.50
C-203	185	SKs 60/40 Pozmix) 250' to Surface	13.40	2479.00
C-206	640#	Gel = 4%	21	134.40
C-108AT		Top Mileage on Bulk Truck	M.C.	345.00
				6,410.90
			- 5%	(341.38)
			Sales Tax	416.71
				6486.23

Authorization by Mike Title owned Total 6486.23

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.