



PAGE	CUST NO	YARD #	INVOICE DATE
1 of 1	1002661	1718	11/01/2019
INVOICE NUMBER			
93080136			

Pratt (620) 672-1201
 B MC COY PETROLEUM CORP
 L PO Box: 39
 L SPIVEY
 T KS US 67142
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME R&S Gates A 1-2
 O LOCATION
 B COUNTY Haskell
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T JOB CONTACT
 E

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41194355	19572		Net - 30 days	12/01/2019

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 10/31/2019 to 10/31/2019</i>				
0041194355				
1718197911 Cement-New Well Casing/Pi 10/31/2019				
Cement PTA				
60/40 Poz	180.00	SK		
Cement Gel	300.00	LB		
Heavy Equipment Mileage	80.00	MI		
Blending & Mixing Service Charge	180.00	SK		
Ton Mileage	310.00	MI		
Depth Charge, 1001'-2000'	1.00	HR		
Light Vehicle Mileage	40.00	MI		
Service Supervisor Charge	1.00	EA		
Driver Charge	2.00	EA		

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TA
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL
DALLAS, TX 75284-1903	FORT WORTH, TX 76102	

D



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	McCoy Petroleum Corporation	Cement Pump No.:	37223 19572 12HRS	Operator TRK No.:	86531
Address:	9342 E. Cemntral	Ticket #:	1718 19791 L	Bulk TRK No.:	27808 19578 Sam
City, State, Zip:	Wichita, Kansas 67206	Job Type:	Z-42 Cement Plug to Abandon		
Service District:	1718-Liberal KS	Well Type:	NEW		
Well Name and No.:	R&S Gates "A" # 1-2	Well Location:	2-30S-31W	County:	Haskell
				State:	Kansas

Type of Cmt	Sacks	Additives	Truck Loaded On		
60/40 Poz	180	4% Total Gel	27808 19578 Sam	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	13.5	1.5	7.5	270	TT Man Hours:	40
Tail:					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
12:30am							Arrived at location
12:45am							Spot trucks/Rig up
3:30am							Safety meeting
4:05am	4	10			200		Pump 10bbls of fresh water
4:10am	3.8	13.3			200		Pump 13.3bbls of cement from 50sks at 13.5lbs
4:17am		22.9			zero		Pump 22.9bbls of mud for displacement
							rig crew pulling drill pipe
5:22am	4	30			200		Pump 30bbls of fresh water
5:30am	4.3	10.6			200		Pump 10.6bbls of cement from 40sks at 13.5lbs
5:34am	4.6	6			zero		Pump 6bbls of displacement
5:40am							rig crew pulling drill pipe
6:24am	1.8	10.6			100		Pump 10.6bbls of cement from 40sks at 13.5lbs
							Cement to Surface
6:39am	1.8	13.3			zero		Pump 13.3bbls of cement from 50sks at 13.5lbs
							to fill rat and mouse hole
							Rig down
							Job Completed
							Thanked company man and rig crew

Size Hole	7 7/8	Depth		TYPE	
Size & Wt. Csg.	8 5/8 24#	Depth		1st plug	1860
Drill pipe	4 1/2 16.6#	Depth		2nd plug	630
Rat and Mouse	50sacks	Type		3rd plug	60

Customer Signature: <i>A. Alan Lott</i>	Basic Representative:	Victor A. Corona
	Basic Signature:	<i>Victor A. Corona</i>
	Date of Service:	10/31/2019