

JOB LOG

SWIFT Services, Inc.

DATE 10-30-19 PAGE NO. 1

CUSTOMER		WELL NO.		LEASE		JOB TYPE		TICKET NO.	
Mustang Energy Corp		#1		Croskell Range		Surface Pipe		032860	
CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS	
				T	C	TUBING	CASING		
	0200								On Location 8 5/8" 23lb/A
									RTD: 306'
	0245								Start 8 5/8" 23lb/ft Casing in well
	0400								Break Circulation
	0415	3 1/2	5		✓	200			Pump 5 bbl H ₂ O Spacer
	0420	4	45		✓	200			⊗ Mix 185 sks of Standard 2% gel 3% CC CMT @ 14.7ppg
	0435	4	0		✓	100			Displace CMT
		4	15 1/2			200			-Circulate CMT to Surface *15Sks to the Pit*
	0445	0	19		✓	300			KO Pump *Shut-in* Release Pressure *HOLD* - Plug down @ 4:45 AM
	0445								Washup Trk #112
	0500								Job Complete
									185 sks of Standard 2% gel 3% CC used - 15 sks to the Pit
									Thank You
									Gideon, Preston, Kirby