



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

19-19-14

FIELD SERVICE TICKET
1718 15273 A

DATE _____ TICKET NO. _____

DATE OF JOB 9/29/14	DISTRICT P...	NEW WELL <input checked="" type="checkbox"/>	OLD WELL <input type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:		
CUSTOMER F.G. 1101	LEASE C9105	WELL NO. 11							
ADDRESS	COUNTY Bevier	STATE MO							
CITY	STATE	SERVICE CREW D... M... C...							
AUTHORIZED BY	JOB TYPE: 242/5 1/2 Long Service								
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	TIME
19873	1						9/29	AM	7:00
19862	1/2						9/29	AM	11:30
							9/29	AM	4:30
							9/29	PM	5:30
							9/29	AM	6:30
						MILES FROM STATION TO WELL	64		

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: _____
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CP105	ADZ Cement	SK	125		
CP103	60/40 P02	SK	75		
CC102	Cello 159c	Lb	32		
CC105	C-41P	Lb	30		
CC111	SS1-	Lb	546		
CC116	Mes Chem 10C12	Lb	354		
CC129	FLA-322	LO	118		
CC201	Gisonic	LO	1384		
CF607	Leica Down Plug Basic, 5 1/2" (Blue)	Eg	1		
CF1251	DV10 Fil Floss shoe	Eg	1		
CF1651	Turnal 200, 5 1/2" (Blue)	Eg	10		
CF1901	5 1/2" Basic (Blue)	Eg	1		
CF2002	Cement Seisochris Pumping Type	Eg	50		
CC154	Super Flux	Gal	500		
F100	Unit Mileage Charge - Pickups	m	65		
F101	Misc. Equipment Mileage	m	130		
F113	Propose 902 Bull's Del... Charge	Min	588		

CHEMICAL / ACID DATA:			

SUB TOTAL	
SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
TOTAL	

SERVICE REPRESENTATIVE <i>[Signature]</i>	THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: <i>[Signature]</i>
--	---

FIELD SERVICE ORDER NO. _____ (WELL OWNER OPERATOR CONTRACTOR OR AGENT)



BASICSM
ENERGY SERVICES
PRESSURE PUMPING & WIRELINE

10244 NE Hwy. 61
P.O. Box 8613
Pratt, Kansas 67124
Phone 620-672-1201

FIELD SERVICE TICKET

1718 ~~15274~~ A

Continuation 1718 15273

19-19-14

DATE TICKET NO.

DATE OF JOB: 9/25/2017		DISTRICT: Pisharies		NEW WELL <input checked="" type="checkbox"/> OLD WELL <input type="checkbox"/>		PROD <input type="checkbox"/> INJ <input type="checkbox"/> WDW <input type="checkbox"/>		CUSTOMER ORDER NO.:			
CUSTOMER: FG Holl				LEASE: C9/C9C9				WELL NO: 2-19			
ADDRESS:				COUNTY: Barton				STATE: KS			
CITY:				STATE:				SERVICE CREW: D Griffin, McGraw, Cobb			
AUTHORIZED BY:				JOB TYPE: 242 / 5 1/2 Long Strings							
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE	AM	PM	TIME	

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).
The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: [Signature]
(WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CE 204	Depth Charge; 3,000' - 4,000'	4pc	1		
CE 240	Blending & mixing Service Charge	SK	200		
CE 504	Plus Contingency Utilization Charge	Job	1		
CE 501	C9C9S Survey Penals	ES	1		
3003	Service Supervisor, First & Trip On/Off	ES	1		

CHEMICAL / ACID DATA:			

SUB TOTAL	
SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$
Discount	TOTAL

SERVICE REPRESENTATIVE: [Signature]

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY: [Signature]
(WELL OWNER OPERATOR CONTRACTOR C)

FIELD SERVICE ORDER NO.

Customer FG 1011	Lease No.	Date 9/29/2017
Lease C9/C919	Well # 2-19	
Field Order # 15273	Station Pratt, KS	Casing 5 1/2
Type Job 242 5 1/2 Long Spring	Depth 3668	County Barton
	Formation TD-3675	State KS
		Legal Description 19-19-14

PIPE DATA		PERFORATING DATA		FLUID USED	TREATMENT RESUME		
Casing Size 5 1/2	Tubing Size	Shots/Ft		Acid	RATE	PRESS	ISIP
Depth 3668	Depth	From	To	Pre Pad	Max		5 Min.
Volume 872	Volume	From	To	Pad	Min		10 Min.
Max Press	Max Press	From	To	Frac	Avg		15 Min.
Well Connection	Annulus Vol.	From	To		HHP Used		Annulus Pressure
Plug Depth 3656	Packer Depth	From	To	Flush KCL WGR	Gas Volume		Total Load

Customer Representative Rob Long	Station Manager Justin Westerman	Treater Darin Francis
Service Units 92911 84981 19893 70959 19862		
Driver Names Darin McGrew McGrew Cobb Cobb		

Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
11:30am					On location / 59 day meeting
					125 SIC PA2 Cement, 1% FLA, .25 Defosmer, 3% mg.s Chem, 10% SS1+ .25 cell flake, 10% Gilsonite
					15.0 pps, 1.43 v.12, 5.22 w.c.w.
					75% below Puz, 2% 601 54 Gilsonite
4:30pm	200		5	5	Pump 5 bbls wgr
	200		12	5	Pump 12 bbls Flush
	200		5	5	Pump 5 bbls wgr
	200		6	5	Mix 25 SIC SBG wgr
	200		32	5	Mix 125 SIC PA2
					Shut down
					Wash pump & lines & Release Plus
	100		0	6	Start displacement
	400		60	6	Lift Pressure
	800		77	3	Slow Rise
5:15pm	1500		85	3	Bump Plug
					Flow - Hold
	30		7	3	Plug Rest hole
					Job complete / Darin & crew
					Thank you!