

CUSTOMER Trans Pacific Oil

WELL NO. 1-27

LEASE Big Fracture Dianne A Surface

JOB TYPE

TICKET NO. 27680

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	2030							On location, set up trucks Rig @ 140' still Drilling
								8 5/8" x 23# 264' of pipe set at 253'
	2230							Start Pipe
	2330							Break Circulation
	2345							Hook up to Swift
		3	5			200		Pump 5 bbl Water ahead
		3						Start Cmt @ 14.7#
	1200	3	41					Fin Cmt, Start Displacement
		3	15 3/4					Fin Displacement, shut down
	1205							shut in, Cmt Circulated
								Release Truck
	1215							Wash up
	1230							Rack up
	1245							Job Complete

Thanks
Jon, Austin, Kirby

RECEIVED
AUG 02 2019

BY:

SWIFT Services, Inc.

DATE 8-9-2019 PAGE NO. 1

CUSTOMER Trans Pacific Oil Co WELL NO. 1-27 LEASE Dianne A JOB TYPE Long String 5/8" TICKET NO. 032532

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0500							On Location 5 1/2" 14lb/ft RTD: 4500' LTD: 4498' PC: 2208' #54 TP: 4493' Turbo: 1, 3, 5, 7, 9, 11, 13, 15, 53 CMT Baskets: 2, 54
	0745 1000							Start 5 1/2" 14lb/ft Pipe in well Drop Ball - Circulate
	1045	6 1/2	12		✓		300	Pump 500 gal Mud Flush
	1050	6 1/2	20		✓		300	Pump 20 bbl KLL Spacer
	1050	2	7		✓		0	Plug Rathole w/ 30 sks
	1055	4	48		✓		200	Mix 170 sks of EA-2 CMT 1/4 lb Flo @ 15.36 ppg
	1105							Drop Latch down Plug - Wash Pump + Lines
	1110	6 1/2	0		✓		200	Start displacement
		6 1/2	77		✓		300	- Lift Pressure
		5 1/2	107		✓		800	- Max Lift Pressure
	1130	0	108.6		✓		1600	Land Latch down Plug
								Release Pressure ★ Hold ★
	1140							Wash up Trk #112
	1215							Job Complete 200 sks of EA-2 CMT 1/4" Flo used
								Thank You,
								Judeen, Preston, & Assoc

8-19-19

CUSTOMER

Trans Pacific

WELL NO.

1-27

LEASE

Dianne A

JOB TYPE

Port Collar

TICKET NO.

27646

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	945							On location
								TOB - 2 7/8 Csg - 5 1/2 port collar - 2211
						1000		Test tools - Held open port collar
		4	0			800		START CNT - 180 sks @ 11.2"
		4	100			850		Circ CNT - Raise wgt to 14" w/g
		4	105			500		End CNT
						1000		Close Port Collar & Test Run 5 Joints
	3.5		21			400		Reverse OUT
								TOOH w/ TOB
								JOB Complete
								Used 205 sks CNT
								Thanks David, Zach & Isaac