

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



API # 15-207-29015

Cement or Acid Field Report
 Ticket No. 1705
 Foreman Shannon Feck
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
9-25-14	1003	Cobble # 9	22	26S	14E	Woodson	KS
Customer <u>Colt Energy, INC</u>			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address <u>P.O. Box 388</u>			SF	105	Dave G		
City <u>Iola</u> State <u>KS</u> Zip Code <u>66749</u>			JS	112	John S		
			DB				

Job Type L/S Hole Depth 1418 Slurry Vol. 44 Bbl Tubing —
 Casing Depth 1359.2 Hole Size 6 7/8" Slurry Wt. 13.7 # Drill Pipe —
 Casing Size & Wt. 4 1/2 @ 10.50 # Cement Left in Casing 4' Water Gal/SK 90 Other —
 Displacement 21 3/4 Displacement PSI 700 Bump Plug to 1100 BPM —

Remarks: Safety meeting, Rig up to 4 1/2" casing. Break circulation, mix 300 # gel flush w/ hulls, 7-8 Bbl H2O spacer, mixed 150SKS Thick Set cement w/ 2 # phenoseal/SK @ 13.7-13.8 #/gal. Shut down wash out pump & lines, displace w/ 21 3/4 Bbl H2O, final pumping pressure of 700 PSI, bump plug to 1100 psi. Good circulation @ all times. 4 Bbl Slurry to pit. rig down Job complete.

" Thank You "
 Shannon & Crew

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	100	100
C107	25	Mileage	100	2500
C201	150SKS	Thickset cement	1200	180000
C208	300 #	Phenoseal @ 2 #/SK	100	30000
C206	300 #	Gel flush	100	30000
C214	45 #	Cottonseed Hulls	100	4500
C108A	8 25 ton	Ton mileage bulk Trk	100	8000
C403	1	1 1/2" Top Rubber Plug	100	100
			Sub Total	27000
			Sales Tax 7.15%	1912.50
Authorization _____ Title _____			Total	28912.50

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.