

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **3082**
Foreman Russell McCoy
Camp Eureka

Date	Cust ID #	Lease & Well Number	Section	Township	Range	County	State
12-15-16	1003	Cobble # 14	22	26	14	wo	ks
Customer Colt Energy Inc.			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 388			Kml A m m str	104	Aladdin		
City Tola				112	Steve		
State KS							
Zip Code 67449							

Job Type Logging **Hole Depth** 1414 **Slurry Vol.** 48 Bbl **Tubing** _____
Casing Depth 1407 **Hole Size** 6 3/4 **Slurry Wt.** 13.8 **Drill Pipe** _____
Casing Size & Wt. 4 1/2 **Cement Left in Casing** 0 **Water Gal/SK** _____ **Other** _____
Displacement 22 1/4 **Displacement PSI** 850 **Bump Plug to** 1400" **BPM** 4

Remarks: Safety meeting + Job Procedure. Rig to 4 1/2 casing, Break
Circulation w/ 5 Bbl fresh water mix + Pump 300" Gel + Halls, Pump 5
water spacer. Mix 155 SK Thickener cement w/ 2" Phenol, wash out lined
+ 4 1/2 Release 4 1/2 Top Rubber Plug. Displace w/ 22 1/4 Rbl water. Final
Pump PSI 850" Pump Plug to 1400" Check float, float held. 3 Bbl cement
slurry to surface. Close 4 1/2 into OPSE. Job Complete, Tear Down.
Thank you
Russell McCoy

API # 15-207-2939L

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge		
C-107	25	Mileage		
C-201	155	SK Thickener cement		
C-208	300"	Phenol = 2" P-7 SK		
C-206	300"	Gel Flush		
C-214	40"	Halls		
C-108A	8.25	Tax mileage		
			Sales Tax	
Authorization <u>Rob Ballou</u> Title <u>SA</u>				Total

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.