

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3549**
 Foreman Rick Ledford
 Camp Eureka 115

API# 15-207-29490

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
10-25-17	1003	Carthage " 40	22	27S	14E	Wc	115	
Customer <u>Coit Energy Inc</u>			Unit #		Driver		Unit # Driver	
Mailing Address <u>P.O. Box 388</u>			144		<u>Adam</u>			
City <u>Iola</u>			110		<u>Steve</u>			
State <u>Ks</u>								
Zip Code <u>66749</u>								

Job Type L/S Hole Depth 1385' Slurry Vol. 48 Cu' Tubing _____
 Casing Depth 1385 Hole Size 6 3/4" Slurry Wt. 13 2" Drill Pipe _____
 Casing Size & Wt. 4 1/2, 11.6 lb Cement Left in Casing 4' 5" Water Gal/SK 9.0 Other _____
 Displacement 22 Cu' Displacement PSI 750 Bump Plug to 1250 BPM _____

Remarks: Safety meeting: Rig up to 4" casing. Break circulation w/ fresh water. Pump 6 gal/gal flush w/ balls. 5' 1/2" water spacer. Mixed 155 sks thickset cement w/ 2" phenoseal 1/sk @ 13 2" /gal. With out pump & lines, release plug. Displace w/ 22 Cu' water. Final pump pressure 750 PSI bump plug to 1250 PSI. Release pressure float & plug held. Good cement returns to surface. 8 Cu' slurry to p.k. Job complete. Rig down.

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge		
C107	25	Mileage		
C201	155 sks	thickset cement		
C202	320"	2" phenoseal 1/sk		
C206	300"	gal flush		
C214	40"	balls		
C102A	8.53	fuel mileage bump plug		
C403	1	4 1/2" top water plug		
			Subtotal	
			Sales Tax	

Authorization R.R. Schlock Title _____

Total

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.