

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3699**
 Foreman Rick Loford
 Camp Eureka Ks

APR 15 - 207-29-22


Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
1-10-18	1003	Landex " 38	23	26	14C	Woodson	Ks	
Customer <u>Coit Energy Inc</u>			Unit # <u>104</u>		Driver <u>Alvin</u>		Unit #	Driver
Mailing Address <u>P.O. Box 388</u>			Unit # <u>113</u>		Driver <u>Sharon</u>			
City <u>Topeka</u>			State <u>Ks</u>		Zip Code <u>66604</u>			

Job Type 1 1/2 Hole Depth 1402 Slurry Vol. 51 Tubing _____
 Casing Depth 1374 Hole Size 6 3/4" Slurry Wt. 1380 Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing 4'51 Water Gal/SK 90 Other _____
 Displacement 22 1/2 Displacement PSI 1021 Bump Plug to 1500 BPM _____

Remarks: Safety meeting. Rig up to 4 1/2 casing. Break circulation w/ fresh water. Pump 6 hrs gel-flush w/ balls. 5 ball water spacer. Mixed 1165 lbs thixot cement w/ 2" phosacid 1/8" 13.2" gel. Washout pipe + line, release plug, Displace w/ 22 1/2 balls fresh water. Final pump pressure 1000 PSI. Bump plug to 1500 PSI. Release pressure. Flood + plug held. Good cement returns to surface. 6 ball slurry kept. Job complete. Rig down.

Note: Mixed 24 hrs gel ball 1 day hold with drilling to TD

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge		
C107	25	Mileage		
C106	2 hrs	misc pump for getting hole		
C206	1300'	gel		
C214	40'	balls		
C201	1165 lbs	thixot cement		
C207	330'	2" phosacid 1/8"		
C206	300'	gel-flush		
C214	40'	balls		
C1080	9.0'	for mileage & extra		
C103	1	4" top anchor plug		
				
			Sub Total	
			Sales Tax	

Authorization R. Ballard Title _____

Total 

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.