

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **2860**
 Foreman Rick Lohr
 Camp Eureka KS

APZ
 15-207-29365

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
825-16	1003	Pendley # 31	22	26	14E	NO	KS
Customer Calt Energy, Inc.			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address 10.358				105	Don G		
City Tola				115	Youn C		
State KS		Zip Code 66749					

Job Type L/S Hole Depth 1446 Slurry Vol. 50 Bbl Tubing _____
 Casing Depth 1436 Hole Size 6 3/4" Slurry Wt. 13.8° Drill Pipe _____
 Casing Size & Wt. 9.5/4.5" Cement Left in Casing 4.53 Water Gal/SK 9° Other _____
 Displacement 23.2 Bbl Displacement PSI 600 Bump Plug to 1000 BPM _____

Remarks Safety meeting. Rig up to 4 1/2" casing. Break circulation w/ fresh water. Pump to 500 gal flush w/ hulls, 5 Bbl water spacer. Mix 150 ses throat cement w/ 2° propanol/hr @ 13.8°/gal. Washout pump + line, release 4 1/2" rubber plug. Displace w/ 23.2 Bbl fresh water. Final pump pressure 600 PSI. Bump plug to 1000 PSI (release pressure, shut & plug held. Good cement returns to surface = 10 Bbl slurry to pit. Job complete. Rig down.

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge		
C107	25	Mileage		
C201	150 ses	throat cement		
C208	300°	2° propanol/hr		
C206	300°	gel-flush		
C214	40°	hulls		
C103A	8.25	for mileage bulk tax		
Sales Tax				
Authorization	Title		Total	

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office