

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. **2943**

Foreman Rick Ladford

Camp Eureka Ks

Date	Cust ID #	Lease & Well Number	Section	Township	Range	County	State
10-27-16	1003	Penley #37				No	Ks
Customer Catt Energy Inc.			Safety Meeting OL OK AB	Unit #	Driver	Unit #	Driver
Mailing Address PO Box 388				105	Dave G		
City Iola				113	Allen B		
State Ks							
Zip Code 66749							

Job Type C/S Hole Depth 1500' Slurry Vol. 50 Bbl Tubing \_\_\_\_\_  
 Casing Depth 1489' Hole Size 6 3/4" Slurry Wt. 13.8# Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2" Cement Left in Casing 4' 37" Water Gal/SK 9.0 Other \_\_\_\_\_  
 Displacement 24 Bbl Displacement PSI 1000 Bump Plug to 1500 BPM \_\_\_\_\_

Remarks: Safety meeting - Rig up to 4 1/2" casing. Break circulation w/ fresh water. Pump 6 sacks gel flush w/ bulls. 5 Bbl water spacer. Mixed 150 sacks thickset cement w/ 2<sup>nd</sup> phase seal 150 @ 13.8#/gal. Washout pump + lines, release plug. Displace w/ 24 Bbl water. First pump pressure 1000 PSI. Bump plug to 1500 PSI. Release pressure, shut & plug hold. Good cement returns to surface = 2 Bbl slurry to pit. Job complete. Rig down.

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge		
C107	25	Mileage		
C201	150 sacks	thickset cement		
C208	300#	2 <sup>nd</sup> phase seal / gal		
C206	300#	gel flush		
C214	40#	bulls		
C102A	8.25	tan mileage bulk tax		
			Subtotal	
			Sales Tax	
Authorization	<u>D. Ballard</u>		Title	Total

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office