

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **3190**
Foreman Rick Letford
Camp Eureka, KS

15-207-29419

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
3-15-17	1003	Schafer # CS-25	23	26	19E	Wagon	Ks
Customer <u>Calt Energy Inc.</u>		Safety Meeting <u>Rick Letford</u>		Unit # <u>105</u>	Driver <u>Don E. Korman</u>	Unit #	Driver
Mailing Address <u>Box 388</u>							
City <u>Tola</u>	State <u>Ks</u>	Zip Code <u>66719</u>					

Job Type L/S Hole Depth 1403 Slurry Vol. 47 BW Tubing _____
Casing Depth 1393.30 Hole Size 6 3/8" Slurry Wt. 13.8" Drill Pipe _____
Casing Size & Wt. 4 1/2" 11.6 lb/ft Cement Left in Casing 4' 35" Water Gal/SK 9.0 Other _____
Displacement 21.5 BW Displacement PSI 600 Bump Plug to 1000 BPM _____

Remarks: Safety meeting. Rig up to 4 1/2" casing. Break circulation w/ fresh water. Pump 6 SKS gel-flush w/ balls. 5 BW water spacer. Mixed 155 bags thickset cement w/ 2" phoscol/150 @ 13.8"/gal. Washout pump + liner release plug. Displace w/ 21.5 BW water. Final pump pressure 600 PSI. Bump plug to 1000 PSI. Release pressure. Plug + plug laid. Good cement returns to surface. 8 BW slurry to pit. Job complete. Rig down.

Thank You

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	2000	2000
C103	25	Mileage	8000	2000
C201	155 bags	thickset cement	1000	155000
C303	310"	2" phoscol psi	1000	310000
C206	300"	gel-flush	800	240000
C214	40"	balls	800	32000
C128A	8.50	for mileage bump 4.00	1000	8500
C403	1	1 1/4" top rubber plug	1000	1000
			Sales Tax	1000
Authorization <u>Rick Letford</u> Title _____			Total	1000

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.