

810 E 7TH  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561

15-207-29331



**Cement or Acid Field Report**  
 Ticket No. 2731  
 Foreman Steve Mead  
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
3-2-16	1000	Schafer # CS-19	23	26	14E	Woodson	KS
Customer		Safety Meeting		Unit #	Driver	Unit #	Driver
Calt Energy Inc				104	Alan M		
Mailing Address				110	Kenn M		
P.O. Box 385							
City	State	Zip Code					
Tola	Ks	66719					

Job Type 45 Hole Depth 1382 Slurry Vol. \_\_\_\_\_ Tubing \_\_\_\_\_  
 Casing Depth 1377 Hole Size 13.25 Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 10.5 #1 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 21 3/4 Displacement PSI 1000 Bump Plug to 1200 BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 4 1/2 casing. Break circulation w/ fresh water. Pump 300' Gel Flush w/ Hulls & 500' water space. Mix 150 SKs Thickset cement w/ 2" phenoseal. Wash out pump & lines. Shutdown. Release plug. Displace w/ 21 3/4 bbls fresh water. Final pumping pressure 1000+ bump plug to 1300'. Release pressure. Plug held. Good cement returns to surface. Shifts to PIT. Job complete. Rig down.

*Thank you.*

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge		
C107	25	Mileage		
C201	150 SKs	Thickset cement		
C208	300'	Phenoseal 2" pipe		
C206	300'	Gel Flush		
C214	40'	Hulls		
C158A	8.25 hrs	Tool mileage Bulk truck		
C403	1	4 1/2" Tap Rubber plug		
			Sub Total	
			Sales Tax	

Authorization [Signature] Title \_\_\_\_\_ Total \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.