

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **4848**  
 Foreman KEVIN MCCOY  
 Camp EUREKA

API # 15-115-21506-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-26-19	1152	Cedar Springs TRUST #2	13	21S	4E	MARION	Ks
Customer			Unit #	Driver		Unit #	Driver
Te-Pe OIL & GAS			104	ALAN M.			
Mailing Address			112	Josh V.			
P.O. Box 522							
City	State	Zip Code					
CANTON	Ks	67428					

Job Type SURFACE Hole Depth 222' K.B. Slurry Vol. 24 BBL Tubing \_\_\_\_\_  
 Casing Depth 207' G.L. Hole Size 12 1/4" Slurry Wt. 15 # Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 9 5/8 36 3/40\* Cement Left in Casing 15' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 15.5 BBL Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 9 5/8" casing. Break circulation w/ 10 BBL fresh water. Mixed 100 SKS CLASS "A" Cement w/ 3% CaCl2, 2% Gel, @ 15 #/gal = 24 BBL slurry. Displace w/ 15.5 BBL fresh water. Shut casing in. Good cement returns to surface = 7 BBL slurry to pt. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 101	1	Pump Charge	890.00	890.00
C 107	30	Mileage	4.20	126.00
C 200	100 SKS	CLASS "A" Cement	15.75	1575.00
C 205	280 #	CaCl2 3%	.63*	176.40
C 206	190 #	Gel 2%	.21*	39.90
C 108 A	4.7 TONS	Ton Mileage	M/c	365.00
			Sub Total	3172.30
			Less 5%	165.33
			Sales Tax	134.35

THANK YOU  
 M

Authorization By TERRY BRANDI Title \_\_\_\_\_ Total 3141.32

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.