



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

100815
41011

TICKET NUMBER 55622 ✓
LOCATION Ottawa KS
FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

INV 101154

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/25/19	4015 ✓	Hayes # I-4 ✓	NW 29	17	22	MU

CUSTOMER
JTC Oil Inc. ✓

MAILING ADDRESS
35790 Plum Creek Rd

CITY
Osawatomie

STATE
KS

ZIP CODE
66064

TRUCK #	DRIVER	TRUCK #	DRIVER
729	Gas Ken	✓	Safety Meeting
495	Har Bee	✓	
804	Kei Det	✓	
369	Ala Mad	✓	

JOB TYPE long string HOLE SIZE 5 7/8" HOLE DEPTH 620' CASING SIZE & WEIGHT 2 3/8" EUE

CASING DEPTH 592' DRILL PIPE _____ TUBING pin - 582' OTHER _____

SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 10'

DISPLACEMENT 2.36 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 100 # Bentonite followed by 5 bbls fresh water, mixed + pumped 60 sks Thixoblend II cement w/ 1 # Pheno seal per sk, cement to surface, flushed pump clean, pumped 2" rubber plug to pin w/ 2.36 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MFT, shut in casing.

[Handwritten signature]

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ CE0450	1	PUMP CHARGE	1500.00	
✓ CE0002		MILEAGE		
✓ CE0711	1/2 min	tax mileage	220.00	
✓ WE0853	1 hr	80 Vac	100.00	
		trucks	1820.00	
		- 45%	819.00	
		Subtotal		1001.00 ✓
5/6/23 ✓ CC5861	60 sks	Thixoblend II cement	1620.00	
✓ CC5965	100 #	Bentonite	30.00	
✓ CC6079	60 #	Pheno seal	81.00	
✓ CP8175	1	2" rubber plug	45.00	
		materials	1776.00	
		- 45%	799.20	
		Subtotal		976.80 ✓
		8%	SALES TAX	78.14
			ESTIMATED TOTAL	2055.94

RAVIN 3737

AUTHORIZATION [Signature] ✓ TITLE _____ DATE (3738.08)

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.