



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

TICKET NUMBER 55620 ✓

LOCATION Offawa, KS

FOREMAN Carey Kennedy

100816
41012

INV 901155

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7/25/19	4015	Shipley # I-1	SE 13	18	21	MI
CUSTOMER JTC Oil Inc.						
MAILING ADDRESS 35790 Plum Creek Rd						
CITY Osawatomie	STATE KS	ZIP CODE 66064				
			TRUCK #	DRIVER	TRUCK #	DRIVER
			729	Cashen	✓ Safety	Meeting
			495	Harbec	✓	
			804	KeiDet	✓	

JOB TYPE long string HOLE SIZE 5 7/8" HOLE DEPTH 540' CASING SIZE & WEIGHT 2 3/8" EVE
CASING DEPTH 494' DRILL PIPE TUBING pin - 484' OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 10'
DISPLACEMENT 1.96 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 100 #
Bentonite followed by 5 bbls fresh water, mixed & pumped 53 sks
Thixobond II cement w/ 1 # Phenoseal per sk, cement to surface,
flushed pump clean, pumped 2" rubber plug to pin w/ 1.96 bbls,
pressured to 800 PSI, shut in casing.

Handwritten signature

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
✓ E0450	1	PUMP CHARGE	1500.00	
✓ E0002	25 mi	MILEAGE	178.75	
✓ E0711	1/2 min	ton mileage	220.00	
		trucks	1898.75	
		-45 %	854.44	
		Subtotal		1044.31 ✓
✓ CC5861	53 sks	Thixobond II cement	1431.00	
✓ CC5965	100 #	Bentonite	30.00	
✓ CC6079	53 #	Phenoseal	71.55	
✓ CP8175	1	2" rubber plug	45.00	
		materials	1577.55	
		-45 %	709.90	
		Subtotal		867.65 ✓
		8%	SALES TAX	69.41
			ESTIMATED TOTAL	1981.37

Ravin 3737

AUTHORIZATION [Signature] ✓

TITLE _____

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.