

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
Ticket No. 4788
 Foreman Russell McCoy
 Camp Eureka

Date	Cust. ID #	Lease & Well Number		Section	Township	Range	County	State
9-27-19	1099	Lehmann A # 8					Coffey	Ks
Customer			Safety Meeting PM	Unit #	Driver	Unit #	Driver	
Quest Development				104	Alan			
Mailing Address				112	Steve			
P.O. Box 413				140	Zevi			
City	State	Zip Code		128	Russell			
TOLA	Ks	66749						

Job Type Logging Hole Depth 1042 Slurry Vol. 33 Tubing 2 7/8
 Casing Depth 1032 Hole Size 5 1/8 Slurry Wt. 14 # Drill Pipe _____
 Casing Size & Wt. _____ Cement Left in Casing 0 Water Gal/SK _____ Other _____
 Displacement 6.1 Displacement PSI 500 Bump Plug to 1000 # BPM 4

Remarks: Safety Meeting, Rig to 2 7/8 Tubing Break Circulation w/ 5 Bbl fresh water Pump to SKS Gel Flush, 10 Bbl water spacer mix 120 cpg owc w/ 1 # Phenoseal per sk @ 14 # per gallon. yield 1.52 = 33 Bbl Slurry SHOT Down wash out Pump + lines stuff 2 Plug's Displace w/ 6.1 Bbl water. Final Pump PSI 500# Bump Plug to 1,000# check float, float tick. 4 Bbl Slurry to Surface. Annulus Full Close in 0 PSI. Job complete, tear down.

THANK YOU
 Russell McCoy

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge	1100.00	1100.00
C-107	50	Mileage	4.20	210.00
C-202	120	SKS OWC cement	20.00	2400.00
C-208	120 #	phenoseal 1 # per/sk	1.30	156.00
C-206	300 #	gel flush	.21	63.00
C-108	6.24	Tow's Tow Mileage Bulk Truck 50 miles	1.40	436.80
C-401	2	2 7/8 TOP Rubber Plugs	30.00	60.00
C-114	3.5	hr water Transport	115.00	402.50
C-224	4.00	gallon city water	10 per/1,000	40.00
				4,868.30
			- 5%	252.25
			Sales Tax	116.94

Authorization witnessed by Hal Title owner Total 4,792.99

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.