

810 E 7th
PO Box 92
EUREKA, KS 67045
(620) 583-5561




Cement or Acid Field Report
Ticket No. **3343**
Foreman Russell McRoy
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
5-25-17	1003	C665) = # 24	22	26	14	Johnson	KS
Customer Colt Energy			Unit # 104		Driver Alan M Zou		
Mailing Address P.O. Box 388			Safety Meeting Rm Alan Zou		Unit #		Driver
City TOLA		State KS	Zip Code 66749				

Job Type L/S Hole Depth 1404 Slurry Vol. 50 Bbl Tubing _____
Casing Depth 1394 Hole Size 6 3/4 Slurry Wt. 13.8 # Drill Pipe _____
Casing Size & Wt 4 1/2 11.60 Cement Left in Casing 0 Water Gal/SK 9 Other _____
Displacement 22 Bbl Displacement PSI 750 Bump Plug to 1300 # BPM 4

Remarks: Safety meeting. Rig to 4 1/2 casing. Break circulation w/ 5 Bbl
water. Mix + Pump 300 # gel w/ 40 # Hulls. Pump 5 Bbl spacer. Mix 165 SK's
Thick set cement w/ 2 # Shovel. P/SK @ 13.8 = 50 Bbl Slurry. WASH OUT
Pump + lines. Release 4 1/2 Top Rubber Plug. Displace w/ 22 Bbl Fresh
water w/ Final Pump PSI @ 750# Bump Plug to 1300# check Float. Float
held. 5 Bbl cement RETURNS to SURFACE. Annulins Stayed Full. Job
complete. Tear Down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge	1000	1000
C-107	25	Mileage	1000	25000
C-201	165 SK's	Thickset cement	1000	165000
C-208	330 #	Shovel = 2" P/SK	1000	330000
C-206	300 #	gel Flush	1000	300000
C-214	40 #	Hulls	1000	40000
C-408A	9.8B	Top Mileage Bulk Truck	1000	9800
C-403	1	4 1/2 Top Rubber Plug	1000	1000
			Sub Total	1000000
			Sales Tax	100000
Authorization <u>called by Job</u> <u>Witnessed by Steve</u> Title <u>Colt Rep</u>			Total	1100000

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office

1317 105th Rd.
Yates Center, KS 66783

Formation Record								
From	To	Formation	From	To	Formation	From	To	Formation
0	15	overbuden						
15	206	shale						
206	475	Lansing Lime						
475	552	shale						
552	733	KC Lime						
733	824	shale						
824	831	lime						
831	838	shale						
838	843	lime						
843	854	sandy shale						
854	864	lime						
864	962	sandy shale						
962	990	lime						
990	1011	shale						
1011	1017	lime						
1017	1054	shale						
1054	1064	sq sand oil show						
1064	1239	sandy shale						
1239	1240	sand oil show						
1240	1269	core						
1269	1280	black sand dead oil						
1280	1412	shale						
1412	1414	Miss Lime						

Well Notes:
Ran 4 1/2" Casing