

Ackarman Hardware & Lumber  
 Ackarman Inc  
 160 East Main St  
 Sedan, KS 67361  
 620-725-3103  
 Fax: 620-725-5688

**CUSTOMER COPY**



**INVOICE**

1801-111282 PAGE 1 OF 1

SOLD TO	JOB ADDRESS
STAN MILLER SM OIL & GAS P. O. BOX 189 SKIATOOK OK 74070	STAN MILLER SM OIL & GAS P. O. BOX 189 SKIATOOK OK 74070 918-396-3020

ACCOUNT	JOB
00680	0
SOLD ON	1/2/2018 4:03:16 PM
CUST PICKUP	
BRANCH	1000
CUSTOMER PO#	TRUST #10
STATION	A1
CASHIER	DK
SALESPERSON	CM
ORDER ENTRY	

Quantity	UM	Item	Description	D	T	Price	Per	Amount
14	EACH	MP10092	PORTLAND CEMENT 92.6#		Y	14.9500	EACH	209.30

Payment Method(s) Buyer: TOM OAST

Charge to Acct 230.23

	SubTotal	209.30
KS 10.00%	Sales Tax	20.93
	Deposit	
<b>Please Pay This Amount</b>		<b>230.23</b>

Signature TOM OAST

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. 3689  
 Foreman KEVIN McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
1-9-18	1180	Trust #10				CO	KS
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
S. M. OIL & GAS, INC.	P.O. Box 189	SKIATOOK	OK	74070	KM DG JH GM	105 110 112 127 P.U.	DAVE G. KEVIN M. JASON H. GREG M.

Job Type Longstring Hole Depth 1630' Slurry Vol. 34 BBL LEAD 20 BBL TAIL Tubing \_\_\_\_\_  
 Casing Depth 1624' Hole Size 6 3/4" Slurry Wt. 12.8\* - 14\* Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 25.5 BBL Displacement PSI 950 Bump Plug to 1400 PSI BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 4 1/2 casing. BREAK CIRCULATION w/ 40 BBL FRESH WATER. Pump 500\* Gel Flush w/ Hulls, 5 BBL water SPACER. MIXED 125 SKS 50/50 Pozmix Cement w/ 6% Gel, 1\* PhenoSeal/SK @ 12.8\*/GAL = 34 BBL SLURRY. TAIL IN w/ 75 SKS OWC Cement w/ 1\* PhenoSeal/SK @ 14\*/GAL = 20 BBL SLURRY. WASH out Pump & Lines. Shut down. Release Plug. Displace Plug to SEAT w/ 25.5 BBL FRESH WATER. FINAL Pumping Pressure 950 PSI. Bump Plug to 1400 PSI. WAIT 2 MINS. Release Pressure. FLOAT Held. Shut in @ 0 PSI. Good Cement RETURNS to SURFACE = 6 BBL SLURRY to Pit. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	125 SKS	50/50 Pozmix Cement	11.25	1406.25
C 206	630 *	Gel 6%	.20 *	126.00
C 208	125 *	PhenoSeal 1*/SK	1.25 *	156.25
C 202	75 SKS	OWC Cement	19.15	1436.25
C 208	75 *	PhenoSeal 1*/SK	1.25 *	93.75
C 206	500 *	Gel Flush	.20 *	100.00
C 214	40 *	Hulls	.45 *	18.00
C108A	9.15 TONS	Ton Mileage BULK TRUCKS X 2	M/c x 2	690.00
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
C 113	3 HRS	80 BBL VAC TRUCK (C & E OIL)	85.00	255.00
C 224	3300 gals	City water	10.00 / 1000	33.00
<u>THANK YOU</u> <u>M</u>			Sub Total	5528.00
			Less 5%	290.92
			Sales Tax 8.5%	290.23
			Total	5527.31

Authorization \_\_\_\_\_ Title \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.