

AP COPY

Quality Well Service, Inc.

**PO Box 468
Pratt, KS 67124**

RECEIVED

OCT 23 2019

Invoice

| | |
|------------|-----------|
| Date | Invoice # |
| 10/22/2019 | 2188 |

| |
|---|
| Bill To |
| Lotus Operating Co. LLC 100 S. Main, STE. 420 Wichita, KS 67202 |

| | | |
|----------|-------|----------------|
| P.O. No. | Terms | Lease Name |
| | | Sterling #1-31 |

| Description | Qty | Rate | Amount |
|---|-----|--------|-----------|
| Rig Time | 18 | 190.00 | 3,420.00T |
| Floor Rental | 1 | 350.00 | 350.00T |
| Rip Casing | 2 | 400.00 | 800.00T |
| Welding | 2 | 75.00 | 150.00T |
| Water Truck | 6 | 90.00 | 540.00T |
| Phone Calls | 1 | 20.00 | 20.00T |
| Clerical | 1 | 25.00 | 25.00T |
| Wiping Rubber | 1 | 20.00 | 20.00T |
| Fresh Water | 2 | 30.00 | 60.00T |
| <p>GL# 9053 DESC. dug + backfill cellar pit, set CIBP, plug w/ cement, pull csg WELL # Ster31</p> | | | |
| <p>Sterling #1-31 Barber Co.</p> <p>10/16/19: Drove to location, rigged up, set bridge plug at 4745', bailed 2 sacks cement on plug, moved pumping unit with backhoe, dug cellar and pit, unpacked casing head, set floor, couldn't get slips to break out of casing head, tried to heat head, ran out of oxygen, drove home.</p> <p>10/17/19: Drove to location, heated up casing, casing got slips to break, cut surface off 4' below ground, loaded hole with water, ripped casing at 3410' and 3240', came free at 3240', pulled casing up to 680', swedged in, drove home.</p> <p>10/18/19: Drove to location, pumped 10 sacks gel, 50 sacks cement at 620', pulled casing to 380', pumped 50 sacks cement, pulled casing to 40', pumped 40 sacks cement to surface, tore down floor and rig, emptied pit, back filled cellar and pit.</p> | | | |

**ENTERED
OCT 29 2019**

| | | |
|------------------------------|-------------------------|------------|
| Thank You for your business! | Subtotal | \$5,385.00 |
| | Sales Tax (7.5%) | \$403.88 |
| | Total | \$5,788.88 |