

JOB LOG

SWIFT Services, Inc.

DATE 11/09/17 PAGE NO. 1

CUSTOMER TDI WELL NO. #10 LEASE Munsch JOB TYPE Cmt LongString TICKET NO. 30546

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1845							On location w/Float Equip
								14# x 5 1/2"
								RTD 3735'
								Total Pipe 3731'
								Baffle Plate @ 3699.45
								D.V. Tool - 1236.5 on #59
								Centralizers - 1, 3, 5, 7, 9, 11, 13, 58
								Baskets - 1, 7, 58
	1900							Start Running Casing/Float Equip.
	2030							Break Circ on Bottom
	2135	4 1/2	12			350		Pump Mudflush
	2140	4 1/2	20			350		Pump KCL Flush
	2145							Pump Cmt - 150 SKS EA-2 @ 15.5 ppg
			36					Fin Cmt, Drop 1st Plug/Wash Pt-L
	2200							Start Disp
			70			500		Catch Cmt
	2215		99 1/4			800/1250		Lift 800 psi Land 1250 psi
	2220							Drop D.V. Bomb
	2235					1700		Open D.V. tool, Pump 3 bbl water
	2240		8					Plug Rathole - 30 SKS SMD
			4					Plug Monshole - 15 SKS SMD
	2245					400		Start Cmt 180 SKS SMD @ 11.2 Ppg
	2310		100			300 500		End Cmt, tail in w/ 13 ppg
	2315							Drop Plug Washout Pt-L
	2320							Start Displ
			8			400		Catch Pressure
	2325		30 1/4			500/900		End Disp Land Plug 900 psi, Lift 500 psi
	2330							Release back Dry
								Wash up truck
	2350							Rack up
								Job Complete
								Thanks,
								Jon, Austin, Kirby