

# GLOBAL OIL FIELD SERVICES, LLC

3192

REMIT TO 24 S. Lincoln  
Russell, KS 67665

SERVICE POINT: Russell

DATE <u>11-10-17</u>	SEC <u>9</u>	TWP. <u>15</u>	RANGE <u>18</u>	CALLED OUT	ON LOCATION <u>5:30 PM</u>	JOB START	JOB FINISH <u>2:30 PM</u>
LEASE <u>Munsch</u>	WELL #. <u>11</u>	LOCATION <u>HAYSERS W INTO</u>			COUNTY <u>ELLIS</u>	STATE <u>KS</u>	
OLD OR NEW (CIRCLE ONE)							

CONTRACTOR Southwind Drbg.

TYPE OF JOB SURFACE

HOLE SIZE 12 1/4 T.D. 218

CASING SIZE 8 1/2 DEPTH 218

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX. MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 15

PERFS

DISPLACEMENT 12 3/4

EQUIPMENT

OWNER

CEMENT AMOUNT ORDERED

150 SY 60/40 3% cc  
2% Gel

COMMON @

POZMIX @

GEL @

CHLORIDE @

ASC @

HANDLING @

MILEAGE @

TOTAL

PUMP TRUCK # CEMENTER Bill

HELPER Jason

BULK TRUCK # DRIVER Bullet

BULK TRUCK # DRIVER

REMARKS:

ran 5 jts of 8 1/2 set c  
cont w/ 1500 cement  
pump plug w/ 12 3/4 bbls of water  
cont did circ.

*Thank*

CHARGE TO: T. D. I. Inc.

STREET

CITY STATE ZIP

Global Oil Field Services, LLC  
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME

SIGNATURE [Signature]

SERVICE

DEPTH OF JOB

PUMP TRUCK CHARGE

EXTRA FOOTAGE @

MILEAGE @

MANIFOLD @

TOTAL

PLUG & FLOAT EQUIPMENT

@

@

@

@

@

TOTAL

SALES TAX (If Any)

TOTAL CHARGES

DISCOUNT IF PAID IN 30 DAYS

JOB LOG

SWIFT Services, Inc.

DATE 11/16/17 PAGE NO. 1

CUSTOMER **TDI** WELL NO. **#11** LEASE **Munsch** JOB TYPE **Cmt Long String** TICKET NO. **30549**

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	2100							On location w/Float Equipment
								5 1/2" x 1 1/2" Casing RTD - 3915 Total Pipe - 3719.88 Baffle @ - 3669.48 D.V. Tool - 1231.63 # 7058 Centralizers - 1, 3, 5, 7, 9, 11, 13, 6957 Basket - 1, 7, 6957
	2300							Start Running Csg / Float Equip
	0230							Break Circ on Bottom
	0330							Drop "Gold" Ball, Set Packer Shoe
	0335	5	12			400		Pump Mud flush
		5	20			400		Pump KCL Spacer
		5	36					Pump Cmt - 150 SKS EA-2 @ 15.5 #
	0355							Drop Plug / Washout PL-L
	0400	7				400		Start Displ.
		7	65			700		Catch Cmt, Pump KCL last 30 bbl
	0415	6	89 1/2			1000 / 1500		Fin Disp / Land Plug Lift - 1000 # Land - 1500 #
								Release back, Dry
	0420							Drop D.V. Bomb
	0425	2 1/2	7					Plug R.H. w/ 30 SKS SMD CMT
	0430	2 1/2	5					Plug M.H. w/ 15 SKS SMD CMT
	0440					1700		Open D.V. Tool
	0445	5				300		Start SMD Cmt - 180 SKS
	0505	5	100			0		End Cmt
	0510							Drop Plug
	0515							Start Disp
	0520		14			400		Catch Cmt
	0520		30			600 / 1300		Fin Disp / Land Plug Lift - 600 # Land - 1300 #
	0525							Release back Dry
	0530							Washing truck, Rackup
	0545							Job Complete Thanks, Jon, Austin, Isaac