

**SM Oil & Gas, Inc.**  
**P. O. Box 189**  
**Skiatook, Oklahoma 74070**  
620-725-3200

January 12, 2018

Kansas Corporation Commission  
Conservation Division  
266 N. Main Street – Suite #220  
Wichita, Kansas 67202-1513


**Re: Trust #11**  
**API #15-019-27605-00-00**  
**Cement Usage ACO-1**

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast  
Area Manager

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. **3721**  
 Foreman Russell McCoy  
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
1-23-18	1180	TRUST # 11				CQ	KS
Customer S.M. Oil + Gas, INC.			Safety Meeting RM DAVE JASON ALAN STEVE	Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 189				105	DAVE		
City SKIATOOK				110	ALAN M		
State OK				112	JASON		
Zip Code 74070				145	Steve		

Job Type Longstring Hole Depth 1829 Slurry Vol. 40 Bbl Lead 20 Bbl Tail Tubing \_\_\_\_\_  
 Casing Depth 1824 Hole Size 6 3/4 Slurry Wt. 12.8 14 # Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing 0 Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 28 3/4 Displacement PSI 900 Bump Plug to 1400 BPM H

Remarks: Safety meeting, Rig to 4 1/2 casing Pump 40 Bbl water no circulation Mix + Pump 500# Gel + Hull's, 5 Bbl water spacer w/ good circulation, shut down 5 min to work out Air on Annulus. Resume Pumping Mix 150 SK's 50/50 light w/ 1# Phenoseal = 40 Bbl Slurry @ 12.8 # w/ yield 1.5 Tail w/ 75 owc cement w/ 1# Phenoseal = 20 Bbl Slurry @ 14 # Shut Down wash out Pump + Lines, Release 4 1/2 Top Rubber Plug Displace Plug to 1824' w/ 28 3/4 Bbl water. Final Pump PSF 900# Bump Plug to 1400# check float float held. 6 Bbl cement slurry to surface. Annulus stayed full. close 4 1/2 IN @ 0 PSI. Job complete, TEAR DOWN.

THANK YOU. Russell McCoy

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge	1050.00	1050.00
C-107	30	Mileage	3.95	118.50
C-204	150	SK's 50/50 Pozmix cement	11.25	1,687.50
C-206	750 <sup>#</sup>	Gel = 6%	.20	150.00
C-208	150 <sup>#</sup>	Phenoseal = 1# Per/SK	1.25	187.50
C-202	75	SK's owc cement	19.15	1436.25
C-208	75 <sup>#</sup>	Phenoseal 1# Per/SK	1.25	93.75
C-206	500 <sup>#</sup>	Gel Flush	.20	100.00
C-214	40 <sup>#</sup>	Hull's	.45	18.00
C-108A	10.16 Ton	Tow Mileage Bulk Truck x 2	m/c x2	690.00
C-113	3 hr	80 Bbl VAC Truck	85.00	255.00
C-224	3,300	gallons city water	10 <sup>per</sup> /1,000	33.00
				5,819.50
Less 5% Sales Tax				< 306.13 > 315.01

Authorization by Joel Potts Title owner Total 5821.18

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.