
McGOWN

DRILLING, INC.

Operator:
N & W Enterprises, Inc.

Forester #4
Crawford Co., KS
34-28-22
API # 15-037-22374-00-00

Spud Date:	2/12/2018	Surface Bit:	9.875"
Surface Casing:	7.0"	Drill Bit:	5.875"
Surface Length:	20'	Longstring:	425.25'
Surface Cement:	4 sx	Longstring Date:	2/13/2018
Longstring:			

Driller's Log

Top	Bottom	Formation	Comments
0	1	Soil	
1	18	Sand Stone	
18	79	Shale	Grey
79	82	Lime	
82	84	Coal	
84	86	Muddy Shale	White
86	115	Lime	
115	118	Blk Shale	
118	148	Shale	Grey
148	156	Sand	Slight oil show (gas)
156	183	Shale	
183	203	Lime	
203	209	Shale	Black
209	215	Lime	
215	215	Shale	
215	217	Lime	
217	376	Shale	
376	377	Coal	Slight odor
377	384	Sand	Good odor, fair bleed to pit, soft sand
384	388	Sand	Good odor, good bleed, laminated sand
388	393	Sand	Good bleed, soft sand, solid, dark brown
393	430	Shale	
430		TD	