

**SM Oil & Gas, Inc.**  
**P. O. Box 189**  
**Skiatook, Oklahoma 74070**  
620-725-3200

February 16, 2018

Kansas Corporation Commission  
Conservation Division  
266 N. Main Street – Suite #220  
Wichita, Kansas 67202-1513


**Re: Wells #1**  
**API #15-019-27608-00-00**  
**Cement Usage ACO-1**

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast  
Area Manager

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. **3761**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
3-2-18	1180	Wells # 1				CQ	Ks	
Customer <u>S.M. OIL &amp; GAS INC</u>			Unit #		Driver		Unit #	Driver
Mailing Address <u>P.O. Box 189</u>			105		DAVE G.			
City <u>SKIATOOK</u>			110		JASON H.			
State <u>OK</u>			113		STEVE M.			
Zip Code <u>74070</u>								

Job Type Longstring Hole Depth 1654' Slurry Vol. 34 BBL LEAD 20 BBL TAIL Tubing \_\_\_\_\_  
 Casing Depth 1650' Hole Size 6 3/4 Slurry Wt. 12.8 - 14 Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 26.2 BBL Displacement PSI 750 Bump Plug to 1250 PSI BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 4 1/2 casing w/ wash head. wash down 8' casing w/ 45 BBL fresh water. Pump 500\* Gel Flush w/ 2 sks hulls, 5 BBL water spacer. Shut down. Rig up Cement Head. Mixed 135 sks 50/50 Pozmix Cement w/ 6% Gel, 1\* PhenoSeal @ 12.8\*/gal, yield 1.42 = 34 BBL slurry. TAIL in w/ 75 sks OWC Cement w/ 3\* PhenoSeal/sk @ 14\*/gal, yield 1.50 = 20 BBL slurry. wash out pump & lines. Shut down. Release Plug. Displace Plug to Seat w/ 26.2 BBL fresh water. FINAL Pumping Pressure 750 PSI. Bump Plug to 1250 PSI. wait 2 mins. Release Pressure, Float Heid. Shut in @ 0 PSI. 2 BBL Cement slurry to Pit. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	135 sks	50/50 Pozmix Cement	11.25	1518.75
C 206	680 *	Gel 6% } Lead Cement	.20 *	136.00
C 208	135 *	PhenoSeal 1*/sk	1.25 *	168.75
C 202	75 sks	OWC Cement } TAIL Cement	19.15	1436.25
C 208	225 *	PhenoSeal 3*/sk	1.25 *	281.25
C 206	500 *	Gel Flush	.20 *	100.00
C 214	80 *	Hulls	.45 *	36.00
C 108	9.57 tons	Ton Mileage BULK TRUCKS x 2	M/C	690.00
C 113	3 HRS	80 BBL VAC TRUCK (C&E OIL)	85.00	255.00
C 224	3300 gals	City water	10.00/1000	33.00
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
			Sub Total	5868.50
			Less 5%	309.38
			8.5% Sales Tax	319.18
Authorization <u>Witnessed By Toby</u> Title _____ Total <b>5878.30</b>				

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.