

SM Oil & Gas, Inc.
P. O. Box 189
Skiatook, Oklahoma 74070
620-725-3200

April 16, 2018

*Kansas Corporation Commission
Conservation Division
266 N. Main Street – Suite #220
Wichita, Kansas 67202-1513*


Re: Wells #4
API #15-019-27611-00-00
Cement Usage ACO-1

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast
Area Manager

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report

Ticket No. **3857**
 Foreman Russell McCoy
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
4-19-18	1180	Wells # 4				CO	Ks	
Customer S.M. OIL + GAS INC.			Unit #		Driver		Unit #	Driver
Mailing Address P.O. Box 189			104		ALAN M			
City SKIA TOOK			115		RUD			
State OK			112		AB			
Zip Code 74070			126		GREG			
Safety Meeting Rm AB ALAN M GREG								

Job Type Long string Hole Depth 1630' Slurry Vol. 34 Bbl lead Tubing _____
20 Bbl Tail
 Casing Depth 1620' Hole Size 6 3/4" Slurry Wt. 12.8 14 # Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing 0 Water Gal/SK _____ Other _____
 Displacement 25 3/4 Displacement PSI 750 Bump Plug to 1300 # BPM 4

Remarks: Safety meeting, Rig to 4 1/2 casing, Break circulation w/ 33 Bbl water, Mix + Pump 500 # Gel w/ Hulls (2 SKs) 5 Bbl water spacer Mix + Pump 135 SKs 50/50 Pozmix w/ 6% Gel 1 # Phenoseal @ 12.8 = 34 Bbl Slurry. Tail w/ 75 SKs o/w cement w/ 3 # Phenoseal / SK @ 14 # w/ yield 1.50 = 20 Bbl Slurry. Shut Down, Wash out Pump + Lines, Release 4 1/2 TOP Rubber Plug. Displace w/ 25 3/4 water Final Pump PSI 750 # Bump Plug to 1300 # Check Float, Float Held. 6 Bbl cement Slurry to Surface. Annulus stayed Full. Job Complete, Tear Down.

THANK YOU

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge	1050.00	1050.00
C-107	30	Mileage	3.95	118.50
C-204	135	SKs 50/50 Pozmix Cement	11.25	1518.75
C-206	680 #	Gel = 6%	.20	136.00
C-208	135 #	Phenoseal 1 # SK	1.25	168.75
C-202	75	SKs o/w cement	19.15	1436.25
C-208	225 #	Phenoseal 3 # SK	1.25	281.25
C-206	500 #	Gel Flush	.20	100.00
C-214	80 #	Hulls	.45	36.00
C-208	9.57	Tow's Tow Mileage x 2	345 m/L	690.00
C-113	3	hr 80 Bbl UAC Truck C+E oil	85.00	255.00
C-224	3,300	gallons city water	10/1,000	33.00
C-403	1	4 1/2 TOP Rubber Plug	45.00	45.00
			Sub TOTAL	5868.50
			Less 5%	309.38
			8.5 % Sales Tax	319.18

Authorization Witnessed by Toby Title Co/Rep Total 5,878.30

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.