

---

---

# McGOWN

DRILLING, INC.

---

---

**Operator:**  
N & W Enterprises, Inc.

**Meyer #40**  
Crawford Co., KS  
33-28-22E  
API # 15-037-22396-00-00

<b>Spud Date:</b>	6/14/2018	<b>Surface Bit:</b>	9.875"
<b>Surface Casing:</b>	7.0"	<b>Drill Bit:</b>	5.875"
<b>Surface Length:</b>	20'	<b>Longstring:</b>	417.'
<b>Surface Cement:</b>	4 sx	<b>Longstring Date:</b>	6/15/2018
<b>Longstring:</b>	2 7/8		

## Driller's Log

Top	Bottom	Formation	Comments
0	2	Soil	
2	4	Clay	
4	14	Sandstone	
14	75	Shale	
75	77	Lime	
77	85	Shale	
85	115	Lime	
115	136	Shale	
136	160	Sandy Shale	
160	165	Grey sand	
165	182	Shale	
182	201	Lime	
201	208	Shale	
208	214	Lime	
214	313	Shale	
313	315	Lime	
315	373	Shale	sandy
373	374	Coal	
374	375	Sand	Laminated sand, good bleed
375	376	Coal	
376	380	Sand	Laminated sand, good bleed
380	389	Sand	Good solid sand, good bleed, soft
389	420	Shale	
420		TD	