



P. O. Box 466
Ness City, KS 67560
Off: 785-798-2300



Invoice

DATE	INVOICE #
6/29/2018	31651

BILL TO
Carmen Schmitt, Inc. P. O. Box 47 915 Harrison Great Bend, KS 67530-0047

- Acidizing
- Cement
- Tool Rental

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#2	Horacek A	Hodgeman	Southwind Drillin...	Oil	Development	Cement 5 1/2 Lo...	David K

PRICE REF.	DESCRIPTION	QTY	UM	UNIT PRICE	AMOUNT
575D	Mileage - 1 Way	60	Miles	5.00	300.00
579D	Pump Charge - Two-Stage & Top To Bottom LongString	1	Job	1,800.00	1,800.00
409-5	5 1/2" Turbolizer	12	Each	85.00	1,020.00T
403-5	5 1/2" Cement Basket	3	Each	275.00	825.00T
406-5	5 1/2" Latch Down Plug & Baffle	1	Each	250.00	250.00T
405-5	5 1/2" Formation Packer Shoe	1	Each	1,350.00	1,350.00T
330	Swift Multi-Density Standard (MIDCON II)	650	Sacks	16.25	10,562.50T
276	Flocele	150	Lb(s)	2.50	375.00T
290	D-Air	7	Gallon(s)	42.00	294.00T
281	Mud Flush	500	Gallon(s)	1.50	750.00T
221	Liquid KCL (Clayfix)	4	Gallon(s)	25.00	100.00T
581D	Service Charge Cement	650	Sacks	1.75	1,137.50
583D	Drayage	1,939.5	Ton Miles	0.85	1,648.58
	Sales Tax Hodgeman County			0.00	0.00
				7.65%	1,187.78

7/19/43
19126.0002
Well Aile
Cement Long String

We Appreciate Your Business!	Total	\$21,600.36
-------------------------------------	--------------	-------------



CHARGE TO: Carmen Schmitt

ADDRESS

CITY, STATE, ZIP CODE

1. SERVICE LOCATIONS <u>Ness City KS</u>	WELL/PROJECT NO. <u>#2</u>	LEASE <u>Horacek "A"</u>	COUNTY/PARISH <u>Hedgerman</u>	STATE <u>KS</u>	CITY <u>Hanston</u>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR <u>Southeast Drilling</u>	RIG NAME/NO. <u>#8</u>	SHIPPED VIA <u>CT</u>	DELIVERED TO <u>Location</u>
3.	WELL TYPE <u>Oil</u>	WELL CATEGORY <u>Development</u>	JOB PURPOSE <u>Cement 5 1/2" Longstring</u>	WELL PERMIT NO.	
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS				

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.	U/M	QTY.
		LOC	ACCT	DF				
<u>575</u>		<u>1</u>			MILEAGE <u>Trk # 112</u>			<u>60</u>
<u>579</u>		<u>1</u>			<u>Pump Change - Top to Bottom Longstring</u>			<u>1</u>
<u>409</u>		<u>1</u>			<u>Turbolizer</u>	<u>5 1/2 in</u>		<u>12</u>
<u>403</u>		<u>1</u>			<u>Cement Basket</u>	<u>5 1/2 in</u>		<u>3</u>
<u>406</u>		<u>1</u>			<u>Latch Down Plug + Baffle</u>	<u>5 1/2 in</u>		<u>1</u>
<u>405</u>		<u>1</u>			<u>Formation Packer Shoe</u>	<u>5 1/2 in</u>		<u>1</u>

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS.

X

DATE SIGNED 6-30-18 TIME SIGNED 0600 A.M. P.M.

REMIT PAYMENT TO:
SWIFT SERVICES, INC.
P.O. BOX 466
NESS CITY, KS 67560
785-798-2300

SURVEY	AGREE	UNDECIDED
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?		
WE UNDERSTOOD AND MET YOUR NEEDS?		
OUR SERVICE WAS PERFORMED WITHOUT DELAY?		
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?		
ARE YOU SATISFIED WITH OUR SERVICE?	<input type="checkbox"/> YES	<input type="checkbox"/> NO
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND		

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services.

SWIFT OPERATOR David Kuchin

APPROVAL [Signature]



PO Box 466
Ness City, KS 67560
Off: 785-798-2300

TICKET CONTINUATION

CUSTOMER: Carmen Schmitt WELL: Horacek A#2

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			TIME	DESCRIPTION	QTY	U/M	QTY	U/M
		LOC	ACCT	DF						
330		1				SMD Cement			650	s
276		1				Floccle	1/4	16	150	lb
290		1				D-Air			7	g
281		1				Mud Flush			500	g
221		1				Liquid KCl			4	g
581		1				SERVICE CHARGE				CUBIC FEET 650
583		1				MILEAGE CHARGE	TOTAL WEIGHT 64650	LOADED MILES 60		TON MILES 1939.5

CO

JOB LOG

SWIFT Services, Inc.

DATE 6-29-18 PAGE NO. 1

CUSTOMER Carmen Schmitt WELL NO. #2 LEASE Horacek "A" JOB TYPE Longstring TICKET NO. #31651

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	2200							on location 5 1/2" 14 #
								RTD- 4594' LTD- 4540'
								TP- 4589' SJ- #1 (#112) 23.23.
								out- #103 #110 #111 Set @ - 4587' (7')
								Turbos- #4 #6 #8 #10 #12 #14 #16 #18 #20 #22 #74 #75
								Baskets- #2 #55 #73
6-30-18	0000							Start 5 1/2" 14 # casing in well
	0230							Circulate
	0310	∅	∅		✓	2000		Set PKR shoe @ 4587' (7' off Bottom)
	0345	6 1/2	12		✓	400		Pump 500 gal Mud Flush
		6 1/2	20		✓	400		Pump 20 bbl HCl Flush
			16-11					Plug RH-MH (30 sks - 20 sks)
	0405	5 1/2	144		✓	400		mix 260 sks SMD @ 11.2 fpg
		5 1/2	43		✓	300		mix 140 sks SMD @ 13.5 fpg
		5 1/2	38		✓	200		mix 100 sks SMD @ 12.5 fpg
		5 1/2	26		✓	100		mix 100 sks SMD @ 14.5 fpg
								Wash out Pump + Lines
								Release Latch Down Plug
	0510	6 1/2	∅		✓	100		Start Displacement
		6 1/2	41		✓	400		Lift Pressure
		6 1/2	96		✓	800		circulate cement to Surface - * 25 sks *
		6 1/2	110		✓	1200		max lift Pressure
	0530	6 1/2	111.5		✓	2000		Land Latch Down Plug
								Release Pressure * Plug Hold *
								Wash up truck
0600	0600							Job Complete
								Thank You
								Dave Preston Gideon Dusky